

REPORT of SURVEY for REPAIRS.

No. 191 Survey held at London Date 19 May to 17 June 1854
 on the Ship Owen Glendower Master W R ~~XXX~~ are
 Tonnage 911 Built at London When built 1839
 By whom built Meyers & Green Owners Messrs Green
 Port belonging to London Destined Voyage Bombay & Ceylon
 If Surveyed Afloat or in Dry Dock Dry Dock, afloat

Last Survey, No. 1836 Port London Classed Cont^d 51 = 4A1¹²

REPAIRS Now Done Metal sheathing stripped - & Hull retrenailed with 13th & 14th Australian treenails from keel to upper part of Males. Siding Helms Continued of Teak along the space between those under fore & main masts through fastened with 1 1/2 inch Gal Metal. Ceiling patched. Two Ballast or Floor Rider Beams of Afr^m Oak applied in way of main mast bottom door through sister & main Helms. Vertical Iron Rider Knees fitted at each end & through bolted with Gal Metal 1 1/2 bolts. 2 pair Iron Riders applied in Lower Hold forward & also one Iron floor rider or crutch - finally vessel hung in shores & caulked from keel to Gunwall & resheathed with Gal Metal over felt.

Present Condition of the

Decks	} <u>efficient</u>	Treenails <u>New from keel to top of Males</u>	Rid ^d Batts	} <u>Good & well formed</u>
Waterways		Breasthooks and Stemson <u>efficient</u>	Windlass and Capstan	
Comings		Transoms, Pointers, and Crutches <u>2^d where seen</u>	Pumps <u>2</u>	
Upper Deck Beams & Fastenings	} <u>efficient</u>	Timbers of the Frame <u>Firm</u>	Boats <u>5</u>	} <u>Good & well formed</u>
Lower Deck Beams & Fastenings		Keelsons <u>Good</u>	Masts, Yards, &c.	
Planksheers	} <u>efficient</u>	Clamps and Shells <u>2^d</u>	Sails <u>full double suit</u>	} <u>Good & well formed</u>
Sheerstrakes		Ceiling <u>efficient</u>	Anchors No. of <u>3 B 1 P 2 K</u>	
Topsides		Rudder <u>2^d</u>	Cables <u>B^d & S^m</u>	
Wales		Copper <u>Gal Metal</u> When put on <u>Now</u>	Hawsers and Warps	
Plank (Bottom) and Counter <u>2^d</u>			Standing & Running Rigging	

General Observations and Opinion, Is in efficient order from well preserved & eligible to remain as classed

Thomas Alexander

The Amount of Fee.....£ 3 : — : is received by me,

Special..... : — : AS

Certificate (if required) : 5 : —

Committee's Minute 14th July 1854

Character assigned Cont^d 4 A 1 Good & well



© 2019

Lloyd's Register Foundation
LON 035 - 0017