

10168

REPORT of SURVEY for REPAIRS.

No. 573 Survey held at London Date 23rd June & 5th July 1854
On the Ship Collingwood Master A Tanner
Tonnage 637 Built at Sunderland When built 1827
By whom built Hay Owners D Dunbar
Port belonging to London Destined Voyage _____
If Surveyed Afloat or in Dry Dock Shrocks Dry Dock & afloat

Last Survey, No. 18335 Port London Classed 10 A1

REPAIRS

Metal Sheathing over Rabbet of stem cut & stripped off to find out cause of leak - piece of forefoot on front of Main stem removed - oakum cleamp out of Rabbet - & lower part of stem for about 16 ft found to have about 3 bolt only. Stem with Hood ends forward all additionally fastened & through bolted with Copper & Jel Met - an additional Breasthook with pointers Ball of Teak applied under Lower deck Hook 4 Orlop Beams of Greenheart applied in Lower Hold & brimed each 2 pair Iron Knives to each Main Mast lifted & 2 ft sleepers on each side of Nelson applied (of Teak) under step Nelson in way of Foremast step partially defective has had the defect cut out & Rader Nelson size to suit over this & otherwise of 7 inch Teak applied - Windlass renewed. New Top mast & Topsail Yard Main Rigging & Stays new - finally Caulked from Metal Sheathing upwards including decks all over

Present Condition of the

Decks		Treenails		Windlass and Capstan	<u>efficient</u>
Waterways	} <u>efficient</u>	Breasthooks and Stenson		Pumps	<u>3</u>
Comings		Transoms, Pointers, and Crutches		Boats	<u>4</u>
Upper Deck Beams & Fastenings	} <u>Good & Firm</u>	Timbers of the Frame	} <u>Good order where seen</u>	Masts, Yards, &c.	<u>new foremast & brass put &c</u>
Lower Deck Beams & Fastenings		Keelsons		Sails	<u>double suit</u>
Planksheers		Clamps and Shelves		Anchors	No. of <u>4 B 1 S 2 K</u>
Sheerstrakes	} <u>efficient where seen</u>	Ceiling		Cables	<u>B & S</u>
Topsides		Rudder		Hawsers and Warps	<u>2</u>
Wales		Copper	<u>Yel Met over felt</u>	Standing & Running Rigging	<u>all as fitted & part new</u>
Plank (Bottom) and Counter	<u>S S S</u>	When put on	<u>1853</u>		

General Observations and Opinion,

Is in Good order from well preserved & eligible to remain as at present classed
Thomas Alexander

The Amount of Fee.....£ : : is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute 8th August 1854

Character assigned 10 A1



© 2019

Lloyd's Register
Foundation

LOW 635-00 69