

# REPORT of SURVEY for REPAIRS.

19175

No. 387 Survey held at London Date 24<sup>th</sup> June to 14<sup>th</sup> July 1854  
 on the Ship Lord Hardinge Master W. Beeby  
 Tonnage 378 Built at Whitehaven When built 1845  
 By whom built L. Kennedy & Co Owners J. Smith  
 Port belonging to Whitehaven Destined Voyage Bombay  
 If Surveyed Afloat or in Dry Dock London for 10 days in Dry Dock

Last Survey, No. 11320 Port Liverpool Classed 12 A 1

## REPAIRS

Metal sheathing stripped removed & renewed on account of local decay. Wing Stemson of 1/2 Oak now of Teak & Counter intermediate timbers & the defective parts at lower ends of any stern timbers cut away & scarphed & replaced all with 1/2 B Oak also Larb<sup>a</sup> Quarter Timbers replaced of B Oak Two 3<sup>d</sup> Futtocks on Port & Three on Starb<sup>a</sup> Quarter renewed of B Oak 14 Hoddies in the Port & 11 on the Starb<sup>a</sup> side renewed of the streaks under & in Wales also in Topsides all of B Oak. One cross counter plank replaced with Teak. Counter plank or Beam inside of timbers renewed of Teak through fastened & iron Anes at ends & fastened finally caulked from Keel to Gunwale & resheathed with Gal Metal over p<sup>r</sup> felt.

## Present Condition of the

Decks	} <u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>SW efficient</u>
Waterways		Breasthooks and Stemson	<u>SW</u>	Pumps	<u>2</u>
Comings		Transoms, Pointers, and Crutches	<u>SW</u>	Boats	<u>3</u>
Upper Deck Beams & Fastenings	} <u>Good: firm</u>	Timbers of the Frame	<u>Good</u>	Masts, Yards, &c.	<u>SW</u>
Lower Deck Beams & Fastenings		Keelsons	<u>SW</u>	Sails	<u>full double sent</u>
Planksheers	} <u>Good</u>	Clamps and Shelves	<u>SW</u>	Anchors	No. of <u>3 B 1 S 1 K</u>
Sheerstrakes		Ceiling	<u>SW</u>	Cables	<u>B. S</u>
Topsides		Rudder	<u>SW</u>	Hawsers and Warps	<u>well found</u>
Wales	} <u>Good</u>	Copper	<u>SW</u>	Standing & Running Rigging	<u>SW</u>
Plank (Bottom) and Counter		<u>SW</u>	When put on <u>Now</u>		

## General Observations and Opinion,

Now in efficient & good order form unaltered & eligible  
As remain as at present classed  
 Thomas Alexander

The Amount of Fee.....£ 2 : — : — is received by me,

Special..... / : / : —

Certificate (if required) — : — : —

Committee's Minute 15<sup>th</sup> August 1854

Character assigned 12 A 1  
Record repair