

# REPORT of SURVEY for REPAIRS.

19176

*Recapping for Asterisk*

No. 569 on the Barb Emily Survey held at London Date July 19<sup>th</sup> to 26<sup>th</sup> 18 54  
 Master Harvey  
 Tonnage 480 Built at Calcutta When built 1836  
 By whom built \_\_\_\_\_ Owners Luscombe &  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock Castors Dry Dock

Last Survey, No. 15884 Port Liverpool Classed 12 A 1 *Clap*  
*C 4 50*

## REPAIRS

Now done, in accordance with the Rules Section 60 the  
 Vessel's sides have been scraped bright from light water mark  
 to the waterway seam, the Yellow Metal sheathing having been  
 stripped off. Greenails and bolts have been driven out from various  
 parts - Two planks on the larboard bilge renewed, having been wormed,  
 vessel hung in shores and caulked from the keel to upper part  
 of Wales. bottom resheathed with Yellow Metal on Felt -

The upper deck and comings, upper and lower deck bolts and  
 the outside plank through which they pass, plank sheers, waterways  
 and beams, hawse timbers, knightheads, breasthooks, transoms, floors  
 keelson, keel, rudder, the planking outside, the frame and inner  
 surface of outside planking where it may be seen all appear in  
 good condition. The sheer and general form of the ship appears  
 to remain unaltered.

Decks <u>good</u>	Treenails	Windlass and Capstan
Waterways <u>scraped</u>	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Orutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>In good order</u>
Lower Deck Beams & Fastenings <u>good</u>	Keelsons <u>All good</u>	Sails <u>and</u>
Plank sheers	Clamps and Shelves <u>where seen</u>	Anchors No. of <u>sufficient</u>
Sheerstrakes	Ceiling	Cables
Topsides <u>scraped, good</u>	Rudder <u>Yellow Metal</u>	Hawsers and Warps
Wales <u>caulked</u>	Copper on Felt <u>When put on how new</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>caulked</u>		

General Observations and Opinion, *The rules having been complied with, we are of opinion*  
*she is eligible to be classed A 1 Asterisk*

The Amount of Fee £ 2 : — : is received by me,

Special..... 3 : 3 : —

Certificate (if required) : 5 : —

Committee's Minute 17 August 18 54

Character assigned A 1 Asterisk Recow repair  
S.S. 54



© 2019

Lloyd's Register  
 Foundation

LOW 635-0078