

REPORT of SURVEY for REPAIRS.

19199

Rec 25/8/54

No. 67 Survey held at London Date July 31st to Aug 9th 1854
 on the Ship "Vernon" Master H. H. Consitt
 Tonnage 911 Built at London When built 1839
 By whom built 996 Owners R. Green
 Port belonging to London Destined Voyage India
 If Surveyed Afloat or in Dry Dock Step^{rs} Green Upper Dry Dock

Last Survey, No. 18390 Port London Classed 12 A 1
 REPAIRS Cont 51 - 14 years

Now done, Yellow Metal stripped off the bottom, the upper course of bottom dubbed bright and examined (to avoid stripping when surveyed for the Asterisk Character) found good; the bottom has been retreenailed from the keel to about the light water mark, with the exception of about twenty feet from each end, keel hung in shores and caulked from the keel to the Black Strake, Bottom resheathed with Yellow Metal on Felt; two planks shifted in the Hold on the starboard side abreast the fore Mast, and one plank in Midships on the

Present Condition of the

Decks <u>Good</u>	Treenails <u>Part renewed</u>	Windlass and Capstan <u>Good</u>
Waterways <u>Caulked</u>	Breasthooks and Stemson	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>Good where</u>	Timbers of the Frame	Masts, Yards, &c. <u>New Fore Mast</u>
Lower Deck Beams & Fastenings <u>seen</u>	Keelsons <u>Good where</u>	Sails <u>Good & sufft</u>
Planksheers <u>"</u>	Clamps and Shelves <u>seen</u>	Anchors No. of <u>"</u>
Sheerstrakes <u>Good where seen</u>	Ceiling	Cables <u>"</u>
Topsides <u>"</u>	Rudder <u>Yellow Metal</u>	Hawsers and Warps <u>"</u>
Wales <u>Caulked good</u>	Copper on Felt <u>When put on how new</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>		

General Observations and Opinion, Having now been well overhauled I am of opinion she is eligible to remain as classed A. 1.

The Amount of Fee.....£ 3 : — : is received by me,

Special..... : — :

Certificate (if required) : 5 : —

Committee's Minute 29th August 1854

Character assigned Cont 4 A 1



© 2019

Lloyd's Register Foundation

00635-0101

