

19265

REPORT of SURVEY for REPAIRS.

No. 191 Survey held at London Date Aug^r to Sept^r 20th 1854
on the Brig "Fortitude" Master PS Murray Jun^r
Tonnage 191 Built at Cochin When built 1845
By whom built Owners D Murray Sen.
Port belonging to London Destined Voyage
If Surveyed Afloat or in Dry Dock In Hatchliff X Dry Dock

Last Survey, No. 17962 Port London Classed 9 A 1

REPAIRS At the present time in conformity with Rule for Continuation Sec No 54. On examining the Iron Bolts in Bottom under small portions of the Wood Sheathing they proved to be wasted, which caused the Yellow Metal and the Wood Sheathing to be stripped off the Bottom. The Planking from light water mark upwards scraped or dubbed bright, a Liston cut from outside Planking in upper course of Bottom extending all Aft on each side to examine Timbers previous to Doubling the original Bottom scathed, caulked, musted Iron Bolts Plugged and the whole of Bottom from Wale to Keel doubled with Red Pine over Felt Yellow Metal fastened with Dumps and through Bolts as prescribed by Rule for Doubling. The Timbers exposed all proved to be sound. The Bottom Sheathed with Yellow Metal over Felt upon the Doubling, Caulked throughout, and the Wale Sheathed with Fir over Felt.

The Duck, Coamings, Deck and Hold Beam Bolts inside and outside Planking, their Fastening Bolts, Planksheer, Watway, Beams, Knives, Sheerstrakes, Plank Heads, Plank Timbers, Keel Keelsons, Floors and Timbers of the frame which they may be seen have been examined by us and appear to be in good condition.

Decks	Keelsons	Windlass and Capstan
Waterways	Bolts	Pumps
Comings	Breasthooks and Stenson	Boats
Upper Deck Beams & Fastenings	Transoms, Pointers, and Crutches	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Timbers of the Frame	Sails
Planksheers	Keelsons	Anchors No. of <u>3, 1, 1</u>
Sheerstrakes	Clamps and Shelves	Cables
Topsides	Ceiling	Hawsers and Warps
Wales	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter	Copper	

General Observations and Opinion,

This Brig has now been "Specially Surveyed" by us in accordance with Rule for Continuation Sec No 54 and we are of opinion that she is in good condition eligible to be

The Amount of Fee £ 2 : : is received by me, Continued A. 1 for 3 Years from 1854.

Special..... 3 : 3 :

Certificate (if required) : 2 : 6

Committee's Minute 16th Sept 1854

Character assigned Coat 1 for 3 Years

Special Fee for Continuation } £ 3.3.0



© 2019

Lloyd's Register Foundation

LOU635-0162