

19318

REPORT of SURVEY for REPAIRS.

Continuation

No. ²⁴⁶ Survey held at London Date Aug^r 26 to Sep 9th 1854
on the Ship "Fortitude" Master Wm Harrison
Tonnage 519 Built at Scarborough When built 1842
By whom built _____ Owners Tindalls
Port belonging to Scarborough Destined Voyage _____
If Surveyed Afloat or in Dry Dock Tindall's dry dock

Last Survey, No. 17309 Port London Classed 12 A. 1.

REPAIRS *Now done, in accordance with the Rules Section 84 the*
keels sides have been scraped bright from the light water mark
to the waterway seam, the yellow metal sheathing being stripped off.
Treenails and bolts have been driven out from various parts for survey.
Treenails in the bilges part renewed. Limber strakes through bolted with
yellow metal extending from the Fore to Main Mast, two stanchions on 2^d side
midships renewed with African Oak, the midship upper deck renewed between
the Main Hatch and Main Mast; Hawse boxes taken out and caulked in
wake of, refitted & bolted; a pair of iron cheeks introduced to the knee
of Head; Bottom resheathed with yellow metal on Felt.

The upper decks and comings, the upper and lower decks
Please turn over

Present Condition of the

Decks <u>part new, good</u>	Treenails <u>part new</u>	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons <u>Good</u>	Sails <u>3 suits good</u>
Planksheers <u>Scraped and</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>4 B. 1 S. 2 K.</u>
Sheerstrakes <u>Caulked</u>	Ceiling <u>"</u>	Cables <u>good & suff.</u>
Topsides <u>"</u>	Budder <u>Yellow metal</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>on Felt</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>Caulked</u>	When put on <u>new</u>	

General Observations and Opinion, *The Rules, Section 84 having been complied with, we*
are of opinion she is eligible to be continued for 4 years A. 1.
from 1854.

The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) _____

Committee's Minute 24th Nov 1854

Character assigned Cont A 1 for 4 years



© 2019

Lloyd's Register
Foundation

LN635-0215

19318 Lon

bolts, and the outside planks through which they pass, plank sheers, waterways, and beams, the lower timbers, and knee heads, breast hooks, and transoms; the floors & keelson; the keel and ladder; the planking outside, and the trimmings passing through from the light water mark upwards; the ceiling inside and the frame and inner surface of the outside planking where it may be seen all appear in good condition.

The sheer and general form of the ship appear to remain unaltered. —

P. Maymouth
Richard Abethey



© 2019

Lloyd's Register
Foundation