

REPORT of SURVEY for REPAIRS.

19425

Repair

No. 371 Survey held at London Date Nov^r 24 to Dec^r 8th 1874
 on the Barque "Himalaya" Master A. B. Rich John Coulson
 Tonnage $\frac{403}{477}$ Built at Sunderland When built 1840
 By whom built _____ Owners G. Marshall
 Port belonging to London Destined Voyage Adelaide
 If Surveyed Afloat or in Dry Dock Left Towson's Dry Dock

Last Survey, No. 18404 Port London Classed SS 52, *A, 1.

REPAIRS

Now done, one Transom renewed, with English Oak, the wing and two other Transoms checked, the upper part of inner post and the two stern timbers to the stern post renewed; nine buttock plank on the S^t and six on the L^d side renewed; five timbers on the S^t Quarter paddled all the above with English Oak. Transoms bolted with 1st Yellow Metal bolts except the wing transom which is bolted with Iron. Bottom Caulked, and the Yellow Metal sheathing renewed on Felt.

Present Condition of the

Decks <u>Good</u>	Treenails <u>Good where</u>	Windlass and Capstan _____
Waterways <u>"</u>	Breasthooks and Stemson <u>seen</u>	Pumps _____
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>pt new</u>	Boats _____
Upper Deck Beams & Fastenings <u>Good where</u>	Timbers of the Frame _____	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings <u>seen</u>	Keelsons _____	Sails <u>sufficient</u>
Planksheers _____	Clamps and Shelves <u>Good where seen</u>	Anchors No. of _____
Sheerstrakes <u>Good where seen</u>	Ceiling _____	Cables _____
Topsides _____	Rudder <u>Yellow Metal</u>	Hawsers and Warps _____
Wales _____	Copper on Felt <u>When put on how new</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion,

She now appears in good and efficient Condition fit for the conveyance of dry and perishable cargoes to and from all parts of the world. And eligible in our opinion to remain classed *A, 1. with Asterisk B - B. W. M. O. L.

The Amount of Fee £ 2 : - : - is received by me,

Special..... : - : -

Certificate (if required) : 5 : -

Committee's Minute 15th December 1874

Character assigned *A, 1 asterisk
ref. app. repair



© 2019

Lloyd's Register
Foundation

LN635-0316