

REPORT of SURVEY for REPAIRS.

19436

No. 436 on the 13th Royal Sovereign Master La Croix Date Nov 21st Dec 1 1854
 Tonnage 350 Built at Jersey When built 1840
 By whom built Deslands Owners Deslands
 Port belonging to Jersey Destined Voyage Calcutta
 If Surveyed Afloat or in Dry Dock In Lavender Dry Dock

Last Survey, No. 18468 Port Louise Classed 9 A 1
53

REPAIRS

Now done. Yellow Metal Sheathing stripped off and renewed upon Paper. Ship hung in thows, Caulked from Keel to Gunwale. From Main Mast Fore the original Riding Keelson (¹⁵ deep) removed being decayed, Main Keelson trimmed over in that space, the unhealthy parts removed, and a new Riding Keelson introduced ¹³ in depth, Bolted with Iron Bolts ¹ Diameter at alternate Frames about half way down the First Butt, which have long Arms, about 20 additional Bolts of ³/₄ Yellow Metal driven into Limber Stakes, at Plank of Deck next the Waterway on each side new.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stemson } <u>Good when seen</u>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>In good order</u>
Lower Deck Beams & Fastenings } <u>d^o when seen</u>	Keelsons <u>repaired</u> <u>d^o</u>	<u>More mast are</u> Sails <u>repacked mast new</u> <u>and sufficient</u>
Planksheers	Clamps and Shells <u>d^o</u>	Anchors No. of
Sheerstrakes <u>d^o</u>	Ceiling <u>d^o</u>	Cables
Topsides <u>d^o</u>	Rudder <u>d^o</u>	Hawsers and Warps
Wales <u>d^o</u>	Copper <u>Yellow Metal</u> When put on <u>now new</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>d^o</u>	<u>or Paper</u>	

General Observations and Opinion,

This Barque now appears to be in good condition,
eligible to remain Classed A

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 : }

Certificate (if required) : 5 : }

Committee's Minute 21st Dec 1854

Character assigned 9 A 1

Regular extra } £2.2.0 W. H. P. H. H.
 attendance }



© 2019

Lloyd's Register
 Foundation

LDN 635-0326