

# REPORT of SURVEY for REPAIRS.

No. 83 Survey held at London Date Dec<sup>r</sup> 14<sup>th</sup> & 16<sup>th</sup> 1854  
 on the Barque "Ada" Master J<sup>r</sup> Gibson  
 Tonnage 311 Built at Yarmouth When built 1825  
 By whom built \_\_\_\_\_ Owners W. Wear  
 Port belonging to Scarborough Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock West India Export Dock

Last Survey, No. 1824 Port Bristol Classed 10 F. 1.  
Rest 38-7 Jw C 3 53

## REPAIRS

The Owner caused a survey to be held on this vessel with a view of getting her class raised to F. 1.

On examination we found it requisite to recommend the following to be done, to make her eligible for the class sought. -

Viz. The decks to be doubled with 2 stuff, the upper deck waterway to be additionally bolted, and pieced where defective; the deck hook and lower hook to be rehooked in the back, the both strakes of Upper deck Clamp to be renewed on the larboard side, extending from forward to the Main Hatch, also one of the upper deck beam ends and one Hold beam end on the L<sup>d</sup> side, and one Upper deck end on the S<sup>t</sup> side to be renewed together with one shift of Shelf and Clamp ranging from the fore to the Main rigging. the rest of the tween Deck ceiling and

Present Condition of the

Decks <u>fair</u>	Treenails <u>Good where seen</u>	Windlass and Capstan
Waterways <u>6</u>	Breasthooks and Stenson <u>defective</u>	Pumps
Comings <u>Good</u>	Transoms, Pointers, and Crutches <u>Good where seen</u>	Boats
Upper Deck Beams & Fastenings <u>part good</u>	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Planksheers	Clamps and Shelves <u>defective</u>	Anchors No. of
Sheerstrakes <u>Good where seen</u>	Ceiling <u>tween Deck defective</u>	Cables
Topsides <u>seen</u>	Rudder <u>fine copper</u>	Hawsers and Warps
Wales	When put on <u>1834</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

We are of opinion that she is eligible to remain as classed F. 1.  
W. Maymouth  
W. L. Goss.

The Amount of Fee ..... £ : : is received by me,

Special ..... : :

Certificate (if required) : :

Committee's Minute 26<sup>th</sup> December 1854

Character assigned F. 1  
[Signature]



© 2019

Lloyd's Register Foundation

LN635-0329



19439 *Lou*

Clamp to be repaired and renewed where necessary. -

The Ceiling in the Hold appears generally good, and the outside planking, as far as we could ascertain, the vessel being afloat. -

The Owner will not enter into the repairs required by us, now, but intimated, it to be his intention to do so, on her return from her present intended voyage (at Scarborough). -

We have given the Owner an account of the above requirements to raise her to the *F.* Character. -

*B. Maymouth*  
*H. C. Goss*



© 2019

Lloyd's Register  
Foundation