

19570

# REPORT of SURVEY for REPAIRS.

No. 20 Survey held at London Date Nov. 2<sup>nd</sup> 1854 to Jan 24<sup>th</sup> 1855  
on the Barque Palestine Master Frederic Sam<sup>l</sup> Bissett  
Tonnage 147 Built at Newcastle When built 1834  
By whom built \_\_\_\_\_ Owners Sam & Co  
Port belonging to London Destined Voyage Antigua  
If Surveyed Afloat or in Dry Dock Rep<sup>rs</sup> Greens Dry Dock and W. India Dock

Survey, No. 17829 Port London Classed 10 A. 1. S.S. 52. \* N.E. 1.  
C 3 52

The Yellow Metal sheathing renewed on Felt, the ship  
hung in shores, and Caulked from keel to the Wales, the lower side  
of keel trimmed up and a false keel added; three broken hanging  
knives on the St<sup>rs</sup> side and two on the Port side renewed.

The following not consequent on damage. - viz<sup>t</sup> A listing  
cut out of the plank under the Wales fore and aft, to examine the  
frame, which was found good; the Wales doubled with 2<sup>nd</sup> Doubling  
the two upper strakes of Teak and the remaining seven strakes of  
Dantzic Deal: The wales Caulked and felted also the Doubling  
Caulked -

## Present Condition of the

Decks <u>Good</u>	Treenails	Windlass and Capstan
Waterways <u>4</u>	Breasthooks and Stems	Pumps
Comings <u>4</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame <u>Good where seen</u>	Masts, Yards, &c. <u>Good and sufficient</u>
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons	Sails
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales <u>Doubled &amp; Caulked</u>	<u>Yellow Metal</u> When put on <u>how new</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>	<u>Copper on Felt</u>	

General Observations and Opinion, She is now in good and efficient Condition, fit for  
the conveyance of dry and perishable Cargoes to and from all  
parts of the World, and eligible to remain (in our opinion) classed  
\* N.E. 1. Asterisk B

The Amount of Fee.....£ 1 : - : - is received by me,

Special..... : : :

Certificate (if required) : 5 : -

Committee's Minute of the February 1855

Character assigned Fit for Asterisk

Special Fee for Damage £44.0