

REPORT of SURVEY for REPAIRS.

Change of Owners

No. 61 Survey held at London Date March 23rd to 29th 1855
 on the Barge "Paradise" Master not appointed
 Tonnage 480 Built at Sunderland When built 1849
321
 By whom built _____ Owners A. Smith
 Port belonging to London Destined Voyage Penang
 If Surveyed Afloat or in Dry Dock Dukeshire Dry Dock

Last Survey, No. 10090 Port London Classed 10 A. 1.
 53

REPAIRS

X Now done, the after piece of keelson renewed with American Oak
 See the Owner's letter intimating that he will replace the whole
 keelson with Teak, on her return from India. - The Yellow Metal
 stripped off the bottom, the keel hung in shores and Caulked from
 the keel upwards including the upper deck; a ^{new} false keel of
 Rock Elm now added - a few of the 1st Deck binding bolts renewed -
 The bottom resheathed with Yellow Metal on Felt. -
 A pair of iron cheeks added to the knee of Head of.

Present Condition of the

Decks <u>Good Caulked</u>	Treenails _____	Windlass and Capstan _____
Waterways <u>"</u>	Breasthooks and Stemson _____	Pumps _____
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>Good where seen</u>	Boats _____
Upper Deck Beams & Fastenings <u>Good where seen</u>	Timbers of the Frame _____	Masts, Yards, &c. <u>Good and suff.</u>
Lower Deck Beams & Fastenings <u>seen</u>	Keelsons <u>After piece renewed</u>	Sails _____
Planksheers _____	Clamps and Shells _____	Anchors No. of _____
Sheerstrakes _____	Ceiling <u>Good where seen</u>	Cables _____
Topsides <u>Caulked</u>	Rudder <u>Yellow Metal</u>	Hawsers and Warps _____
Wales _____	Copper on Felt <u>When put on how new</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion, She now appears in good and efficient Condition, and
eligible in my opinion to remain classed 10 A. 1. and should the
Committee be satisfied with the Owner's intimation she may
remain as classed 10 A. 1. B. Mayhew auth

The Amount of Fee.....£ 1 : - : is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 17th April 1855

Character assigned 10 A. 1.

Record repair with Am. Oak



© 2019

Lloyd's Register
Foundation

LN635-10 486