

19640

REPORT of SURVEY for REPAIRS.

Change of Owners &c

No. 176 Survey held at London Date Apr 10th to 17th 1855
on the Ship Virginia Master Pier
Tonnage 700 Built at St. Johns When built 1845
By whom built 33 Owners Walton &
Port belonging to London Destined Voyage London &c
If Surveyed Afloat or in Dry Dock Union Dry Dock
pt E & S. 52 vv. E & S. 52

Last Survey, No. 11464 Port Liverpool Classed S.S. 52-4 gr. 1.

REPAIRS now done, four topside planks on the L^d side renewed in the way of the Fore, Main & Mizzen Chain bolts; nine planks of topside renewed on the S^t side also all the Main, Mizzen and Fore Chain bolts, the Preventer plates lengthened and rebolted; a portion of the L^d Deck shelf bolts renewed with 1 1/2 Iron - eight Rider bolts renewed, and the three lower strakes of boot topping on each side. One of the S^t after knee riders broken in the throat, an Iron knee has been added in lieu of it - a short piece of the keel for a shifted with E. Elm on account of worm - Pillars in the Hold made good - The Yellow Metal has been renewed on Felt, and the keel caulked from the keel to the Plank sheer. -

Present Condition of the

Decks	<u>Good</u>	Treenails		Windlass and Capstan	
Waterways	<u>4</u>	Breasthooks and Stemson		Pumps	
Comings	<u>4</u>	Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame	<u>Good where</u>	Masts, Yards, &c.	<u>Good and</u>
Lower Deck Beams & Fastenings	<u>where run</u>	Keelsons	<u>run</u>	Sails	<u>sufficient</u>
Plank sheers		Clamps and Shelves		Anchors No. of	
Sheerstrakes		Ceiling		Cables	
Topsides	<u>Caulked</u>	Budder		Hawsers and Warps	
Wales		<u>Yellow metal</u>		Standing & Running Rigging	
Plank (Bottom) and Counter		<u>Copper on Felt</u>	When put on <u>now new</u>		

General Observations and Opinion, She now appears in good condition, fit for the safe conveyance of dry and perishable Cargoes, and eligible to be reentered Ex. 1. B. Weym auth

The Amount of Fee.....£ 2 : : is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute 4th May 1855

Character assigned Ex. 1 record