

REPORT of SURVEY for REPAIRS.

Restoration

No. 17910 Survey held at London Date March 10th to May 1st 1855
 on the Brig "Africanus" Master G.B. Lee
 Tonnage 485 1/2 Built at Parmouth When built 1838
 By whom built 183 1/2 Per Messrs Foster & Smith Owners Foster &
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Messrs Youngs' Dry Dock

Last Survey, No. 17910 Port London Classed 12 Δ New E.A.
 C 4 52

REPAIRS

Now done, in accordance with the Rules, Section 56 the vessel's sides have been scraped bright extending from the light water mark to the Waterway seam, all the upper and lower deck bolts driven out, Planksheers, Waterways, Sheer Strakes, Top-sides and Wales stripped off, also a strake of plank in the upper course of bottom, on each side taken out, and a plank in the bilge each side, inside, and almost the whole of the upper deck - The following are the items renewed viz Twenty eight T. Timbers on the L^h side and thirty six on the Starboard side, of English Oak, eighteen Roughtrees of African Oak each side, four strakes of Wale each side of Dantzic Oak, two strakes of Topside of Dantzic Fir, Sheer strake of African Oak

Present Condition of the

Decks <u>New Caulked</u>	Treenails <u>Good</u>	Windlass and Capstan
Waterways <u>New Caulked</u>	Breasthooks and Stemson <u>Good</u>	Pumps
Comings <u>New</u>	Transoms, Pointers, and Crutches <u>Good</u>	Boats
Upper Deck Beams & Fastenings <u>Renewed with Jam</u>	Timbers of the Frame <u>Part New</u>	Masts, Yards, &c. <u>Good and Sufficient</u>
Lower Deck Beams & Fastenings <u>Renewed with 3 Metals</u>	Keelsons <u>Good where seen</u>	Sails
Planksheers <u>Renewed & Caulked</u>	Clamps and Shelves <u>"</u>	Anchors No. of
Sheerstrakes <u>" & Caulked</u>	Ceiling <u>Part New</u>	Cables
Top-sides <u>" & Caulked</u>	Rudder <u>New Main Piece</u>	Hawsers and Warps
Wales <u>"</u>	<u>Copper on paper</u> When put on <u>Now New</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion, The Rule, Section 56 for Restoration has been complied with, and we are of opinion that she is eligible to be marked in the Registry book, as Restored 1838 for 7 years D.P.

The Amount of Fee.....£ 2 : - : - is received by me, M. Wymouth

Special..... 10 : 10 : -

Certificate (if required) : : -

Committee's Minute 19th June 1855

Character assigned Rest 1 for 7 Years



© 2019

Lloyd's Register Foundation

Lon 636-0038

19742 Lon

One Strake in the upper course of bottom of Dantzic Oak.
 Four planks in the Carboard buttock and five in the Starboard
 buttock of English Oak, Waterway of Dantzic Fir. Planks here
 of African Oak, Main piece of Rudder of English Oak.
 One Hawse timber St side and two on the Carboard side of African.
 St Knight A^d of African, Counter Timber on each side of
 English Oak, a plank each side in the bilge and fore
 woods of the Ceiling of Dantzic Oak, One Upper Deck beam
 end of African Oak, Head Knees and all attached renewed.
 The greater portion of the Upper deck with Dantzic fir -
 Hatchways, Rongtree rail and Main bulwark all new; the
 Vessel Caulked throughout and the bottom resheathed
 with Yellow Metal on paper. —

B. Maym^{outh}

J. H. H. H.



© 2019

Lloyd's Register
Foundation