

# REPORT of SURVEY for REPAIRS.

No. 129 Survey held at London Date April 5<sup>th</sup> 1855  
 on the Barge "Surge" Master McFarrie  
 Tonnage 411 Built at Sunderland When built 1843  
 By whom built \_\_\_\_\_ Owners Phillipps  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock Mr. Wigram's Dry Dock

Last Survey, No. 18710 Port London Classed 10<sup>th</sup> 1/1  
 REPAIRS now done Cont 53, 3 years

The Yellow Metal stripped off the bottom, and the wood sheathing extending from the keel to the 2<sup>nd</sup> futtock heads. Rudder renewed. Main piece of English Oak, Head, Stem and 2<sup>d</sup> Gallies repaired. Catheads renewed with African Oak, three Longtrees renewed in St. waist, three on the poop and two on the Forecastle also two on the larboard side of Forecastle. All the Waist Roughtree Nail renewed, also the Forecastle; A pair of Staple Standard knees introduced to the breast-beam of the Poop in lieu of hanging knees, a part of the Staple Standard knee bolts renewed.

Present Condition of the

Keels	<u>Caulked</u>	Treenails		Windlass and Capstan	
Interways	<u>"</u>	Breasthooks and Stenson		Pumps	
Rings	<u>"</u>	Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	<u>Good</u>	Timbers of the Frame		Masts, Yards, &c.	<u>Good and sufficient</u>
Lower Deck Beams & Fastenings	<u>where seen</u>	Keelsons	<u>Good when seen</u>	Sails	
Plank-sheers		Clamps and Shelves		Anchors No. of	
Deerstrakes	<u>Caulked</u>	Ceiling		Cables	
Sides		Rudder	<u>Renewed</u>	Hawsers and Warps	
Tales		<u>Yellow Metal</u>		Standing & Running Rigging	<u>new</u>
Link (Bottom) and Counter	<u>pt. Caulked</u>	Copper	When put on <u>new</u>		

General Observations and Opinion, The wood sheathing should be marked in the Registry book, as part new 1853- she now appears in good and efficient condition, fit in our opinion to remain Classed A. 1.

The Amount of Fee.....£ / : : is received by me,  
 Special..... : :  
 Certificate (if required) : 5 : -

Committee's Minute 19<sup>th</sup> June 1855  
 Character assigned Cont 3<sup>rd</sup> 1  
Recd. Repair



19746 Lion

*A. W. Ritchie*