

REPORT of SURVEY for REPAIRS.

19840

& Change of Owners

No. 170 Survey held at London Date 27 July 1855
 on the Ship Nimrod Master Tillman
 Tonnage 943 Built at Muramachu When built 1853
 By whom built _____ Owners Tague & Smith
 Port belonging to London Destined Voyage Adelaide
 If Surveyed Afloat or in Dry Dock Fletcher's Dry Dock

R. B. M. G.

Last Survey, No. 12398 Port Liverpool Classed 7 A1

REPAIRS at present time on account of wormed planking - On Starboard side - removed 8 planks of Wales - and 2 shafts outer thickness of after Hoods in Wales - all renewed of Pitch Pine On Port side 8 planks in Wales and outer thickness of 2 after Hoods all replaced anew with Pitch pine & fastenings of lower deck & in way of new planking renewed - 4 streak wood sheathing also part in way of Bullocks taken off - 7 seams (upper courses, wales) caulked - Wood sheathing where removed replaced with new in all 7 streak over felt of additional height over wales & metal raised two sheets in height - and in bottom patched - New Mizen Mast &

Is there any of the wood sheathing of 1853 remaining on? Yes there is
T.M.

Present Condition of the

Decks	} <u>Good</u>	Treenails	<u>Good</u>	Windlass and Capstan	<u>efficient</u>
Waterways		Breasthooks and Stenson	} <u>Good</u> <i>super seen</i>	Pumps	<u>2</u>
Comings	Upper Deck Beams & Fastenings	Transoms, Pointers, and Crutches		Boats	<u>3</u>
Lower Deck Beams & Fastenings	} <u>Good</u>	Timbers of the Frame	<u>Good</u>	Masts, Yards, &c.	<u>2</u>
Planksheers	} <u>Good</u>	Keelsons		Sails	<u>well found</u>
Sheerstrakes		Clamps and Shelves	} <u>Good order</u>	Anchors	No. of <u>3 B 1 S 2 K</u>
Topsides	Ceiling	Rudder		Cables	<u>13' 0" S</u>
Wales		Copper <u>Yel Met</u> When put on <u>1853</u>	Hawsers and Warps	<u>8 1/2 1 5 1/2 5 5 0</u>	
Plank (Bottom) and Counter	<u>2" when seen</u>	Caulking of Bottom, Deck, & Waterways	Standing & Running Rigging	<u>2 0</u>	

General Observations and Opinion,

This vessel is now in an efficient condition and eligible to remain as classed A1

Thomas Alexander

The Amount of Fee.....£ 2 : - : - is received by me,

Special..... £ : £ : -
 for Attendance.

Certificate (if required) _____

Committee's Minute 10th August 1855

Character assigned 7 A1 second repair

T.M.



© 2019
 Lloyd's Register
 Foundation
 LON636-0136