

# REPORT of SURVEY for REPAIRS.

No. 394 on the S. Bristol Survey held at London Date 28 July & 14 Aug 1855  
 Master W. Barrett  
 Tonnage 121 Built at London When built 1831  
 By whom built                      Owners Banzer Brothers & Co  
 Port belonging to London Destined Voyage Cape Coast  
 If Surveyed Afloat or in Dry Dock Fletcher's Dry Dock

Last Survey, No. 18086 Port London Classed A. 1.

## REPAIRS

at present time under special survey with a view to Classification under the Rules Section 56 asterisk character  
 Metal sheathing stripped off - planking scraped or clutched bright from the Light line to inner edge of Waterways - a few trenails & bolts driven out - found efficient  
 Removed & renewed 22 ft Plank sheer on Starb & 17 ft on Port side with Teak & Battie Oak - On Port side 3 planks in Topsides 60 ft Black streak & 3 Woods aft in Wales with Dantzoe Oak & Fir On Starb side 4 planks & Woods in Wales 40 ft Black streak & 2 planks in Topsides 42 ft with Dantzoe Fir & Oak - 4 Bulwark Stanchions of Brit Oak 12 ft Rough tree rail 31 ft Counter berthing of Dantzoe Fir Stern Plank sheer of Pitch Pine Quarter pieces off refitted & part renewed. Finally trenails searched & a few renewed. Rudder Hangings off two braces & one pinth band new & all refastened bottom part of keel dressed - Caulked from keel to Mafts & resheathed with Yel<sup>m</sup> Met over part felt & part paper

## Present Condition of the

Decks		Treenails	<u>efficient</u>	Windlass and Capstan	<u>efficient</u>
Waterways	} <u>efficient</u>	Breasthooks and Stemson	<u>Good</u>	Pumps	<u>2</u> <u>D</u>
Comings		Transoms, Pointers, and Crutches	<u>D</u>	Boats	<u>2</u> <u>D</u>
Upper Deck Beams & Fastenings	} <u>Good &amp; Firm</u>	Timbers of the Frame	<u>Firm</u>	Masts, Yards, &c.	<u>D</u>
Lower Deck Beams & Fastenings		Keelsons	<u>Good</u>	Sails	<u>well found</u> <u>D</u>
Plank sheers	} <u>Good</u>	Clamps and Shelves	<u>D</u>	Anchors	No. of <u>3 B 1 S 1 H</u> <u>D</u>
Sheerstrakes		Ceiling	<u>D</u>	Cables	<u>B</u> <u>D</u>
Topsides		Rudder	<u>D</u>	Hawsers and Warps	<u>7. 5</u> <u>D</u>
Wales	} <u>Good</u>	Copper	<u>Yel<sup>m</sup> Met</u> When put on <u>now</u>	Standing & Running Rigging	<u>D</u>
Plank (Bottom) and Counter					

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways recaulked

This vessel is now in efficient condition sheer and form well preserved eligible to carry dry & perishable cargoes to & from all parts of the world and be classed A. 1 asterisk

The Amount of Fee.....£ 10 : 0 : 0 is received by me,

Special..... 3 : 3 : 0

Certificate (if required).....

Committee's Minute 4<sup>th</sup> September 1855

Character assigned A. 1 asterisk, S.S. 35

Record repair



© 2019

Lloyd's Register Foundation

LON636-0172