

# REPORT of SURVEY for REPAIRS.

19966

No. 76 Survey held at London Date 31<sup>st</sup> Oct<sup>r</sup> 1855  
 on the Ses. Alca Master J Brown  
 Tonnage 127 Built at London When built 1844  
 By whom built \_\_\_\_\_ Owners Northcote &  
 Port belonging to London Destined Voyage Mogador  
 If Surveyed Afloat or in Dry Dock Youngs Dry Dock

Last Survey, No. 1821 B Port London Classed 11. A1

REPAIRS at present of damage incurred by striking upon Margate sand while proceeding on her voyage from London to Mogador more of particulars in special report -  
 Metal sheathing stripped off the post & a portion of the adjoining plating - the keel set up close to the heel of post & additionally bolted together the structural plates removed refitted & fastened - planks in deck connected with post set down where started & fastened finally rabbet & seems adjoining uncovered recaulted & the Metal sheathing when stripped replaced with new - Bower anchor stock (broken) repaired Not of damage 5 seams on each side above metal sheathing recaulted

Present Condition of the

Decks	} Good	Treenails	} efficient	Windlass and Capstan	} efficient
Waterways		Breasthooks and Stenson		Pumps	
Comings	} Good & Firm	Transoms, Pointers, and Crutches	} where seen	Boats	2
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Keelsons		Sails	well found
Planksheers	} Good order where seen	Clamps and Shelves	} seen	Anchors	No. of 2 B 1 S 1 K
Sheerstrakes		Ceiling		Cables	13
Topsides		Rudder		Hawsers and Warps	well found
Wales		Copper	Yel Met When put on 53	Standing & Running Rigging	
Plank (Bottom) and Counter					

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Firm

This vessel is now in efficient condition & eligible to remain as classed A1.  
 Thomas Alexander

The Amount of Fee.....£ : 10 : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 2 : 6

Committee's Minute 16<sup>th</sup> October 1855

Character assigned 11 A1

Record Repair  


Special fee & Report £2.2



© 2019 Lloyd's Register Foundation