

REPORT of SURVEY for REPAIRS.

20022

No. 504 Survey held at London Date 19 Sept to 19 Oct 1855
 on the Barc Andromache Master
 Tonnage 468 Built at Scarbro When built 1828
 By whom built Owners Tobbutt &
 Port belonging to London Destined Voyage
 If Surveyed Afloat or in Dry Dock in Limekiln dry Dock

Last Survey, No. 12228 Port Liverpool Classed Reg C^o 10
Rest 45 1/2
Cent 1
A. 1.

REPAIRS at present under special survey rules Section 50 with a view to Classification upon the Asterisk -- Metal & Wood sheathing stripped off - dubbed & scraped bright - from light line to inner edge of Waterways - treenails & bolts in upper & Lower deck binding driven out for inspection - Removed & renewed on account of natural decay Two Shifts plank in Upper Courses of bottom on Starb side & Two on Port side with Brit Oak - one Shift in Topsides - Starb side of Brit Oak retreenailed from Planksheer down six streak under Wakes with Brit Oak treenails - Streak of deck plank on both sides next waterway renewed of Dantye Pine 3 Hold Beams renewed of Pitch Pine & four others each scarph'd on one end & renewed with Pitch Pine & Dantye Oak - & Ropes in connection refastened - 4 pair new Hang Iron Rope Riggers applied fast with Gal Metal - Ceiling patch'd & rep'd - Foremast tongued & step renewed finally Hinged in shores Caulked from Keel to Gunwall & part decks - Seams of bottom Chum Butts & Keel seam & tested & bottom Wood sheathed with 1 inch pine over felt from Keel to Wakes & resheathed with Gal Metal In removing the above - the Main deck & Comings upper & Lower deck bolts & the outside planks through which they passed - plank sheers Waterways see other side

Present Condition of the

Decks	Good	Treenails	Renewed from Light line up	Windlass and Capstan	efficient
Waterways	Good	Breasthooks and Stemson	Good	Pumps	4
Comings	Good	Transoms, Pointers, and Crutches	Good	Boats	4
Upper Deck Beams & Fastenings	Good &	Timbers of the Frame	Firm where seen	Masts, Yards, &c.	Good
Lower Deck Beams & Fastenings	Firm	Keelsons	Good	Sails	well found
Planksheers	Good order	Clamps and Shelves	Good	Anchors	No. of 3 B 1 S 1 K
Sheerstrakes	Good order	Ceiling	Good	Cables	B & S
Topsides	Good order	Rudder	Good	Hawsers and Warps	Five
Wales	Good order	Copper	Gal Metal When put on Now	Standing & Running Rigging	Good
Plank (Bottom) and Counter	Good				
Felled & Wood sheathed	Good				
General Observations and Opinion,					

Caulking of Bottom, Deck, & Waterways. efficient

Has now been specially surveyed in accordance with the Rules Section 50 for Classification on the Asterisk being in firm & good condition. Firm well preserved eligible in our opinion to carry dry & perishable cargoes to & from all parts of the world We recommend her to be Classed A. 1 asterisk & Marked S.S.

The Amount of Fee.....£ 1 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 5 : -

Committee's Minute 20th November 1855

Character assigned A. 1 asterisk

S.S. 55
 record repair
 J. J.



© 2019

Lloyd's Register Foundation

and beams House timbers Knightheads Hooks & Tronsons floors
& Keelsons Keel & Rudder Frame timbers planking outside
Ceiling Shelves & Clamps & inner surface of outside plank where
seen were all in very sound & efficient condition
T.A.

20022 Lon

