

Annual REPORT of SURVEY for REPAIRS.

20049

No. 458 Survey held at London Date 21st Nov^r 1855
 on the Ship Chrysolite Master M^r Silland
 Tonnage 564 Built at Aberdeen When built 1831
 By whom built A Hall & Co Owners Taylor Potter & Co
 Port belonging to Liverpool Destined Voyage China
 If Surveyed Afloat or in Dry Dock Young Son & Co Dry Dock & afloat

Last Survey, No. 12956 Port Liverpool Classed 14 A1

REPAIRS

at present docked for the purpose of examining bottom
 now done - metal patched - renewed on Starb side 4 Rough
 trees of Brit Oak 38 ft - Rough tree rail & about 25 ft full
 depth of Bulwarks (damage from bad weather) - 8 pair
 Iron Hauling Knives applied to top Gallant-forecastle Beams
 4 pair Iron Riders 2 pair Knee Riders & 1 pair Knives applied
 to Deck Beams the riders extending from the up' deck Beams to
 below floor heads - rigging refitted &c.

Present Condition of the

Decks	} <i>Good</i>	Treenails	}	Windlass and Capstan	<i>2 DW efficient</i>
Waterways		Breasthooks and Stemson		Pumps	<i>4</i>
Comings	} <i>Good</i>	Transoms, Pointers, and Crutches	} <i>Good</i>	Boats	<i>3</i>
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	<i>D</i>
Lower Deck Beams & Fastenings	} <i>Firm</i>	Keelsons	} <i>where</i>	Sails	<i>well found</i>
Planksheers		Clamps and Shelves		Anchors	No. of <i>3 B 1 P 2 K</i>
Sheerstrakes	} <i>Good order</i>	Ceiling	} <i>seen</i>	Cables	<i>B & P</i>
Topsides		Rudder		Hawsers and Warps	<i>well found</i>
Wales	} <i>Good</i>	Copper	} <i>Yel Met.</i>	Standing & Running Rigging	<i>D</i>
Plank (Bottom) and Counter		When put on			

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. firm where seen

This vessel appears in very firm & efficient condition
 the riders now applied not being required on account
 of any visible appearance of working &c. eligible to remain
 as Classed A1

Thomas Alexander

The Amount of Fee.....£..... is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute 7th December 1855

Character assigned 14 A1



© 2019

Lloyd's Register
Foundation