

# REPORT of SURVEY for REPAIRS.

Continuation

No. 11 Survey held at London Date Nov 17 from 6 1855  
 of the Schooner "Peace" Master G. Briggs  
 Tonnage 106 Built at Risnt When built 1845  
 By whom built \_\_\_\_\_ Owners Rawling &  
 Port belonging to Misbeach Destined Voyage Coasting  
 If Surveyed Afloat or in Dry Dock Gun Dry Dock

Last Survey, No. 17020 Port London Classed 10 1

## REPAIRS

Now done, in accordance with the Rules, Section 54 for Continuation the vessel's sides have been scraped bright from the light water mark to the Waterway seam - Ironails and bolts have been driven out for survey. - The After hood of sheer strake on each side has been renewed with English Oak, and all the ironails extending from the lower part of the Wale upwards; graving pieces let into the After end of the keelson where supply, the vessel caulked from the lower part of the Wale upwards. - The upper deck and Comings, the upper deck bolts and the outside planks thru' which they pass, the plank sheers, waterways, and beams, the house timbers, knightheads, breasthooks, and transoms, the floors and keelsons, the keel and rudder, the planking outside, and the ironails passing thru' from the light water mark upwards, the ceiling inside, and the frame and inner surface of the outside planking where it may be seen all appear in good condition, and the sheer and general form of the vessel remain unaltered. -

Decks	Good	Treenails	Renewed	Windlass and Capstan	
Waterways	" scraped	Breasthooks and Stemson	Good	Pumps	
Comings	Good	Transoms, Pointers, and Crutches	"	Boats	one in No
Upper Deck Beams & Fastenings	Good	Timbers of the Frame	Good where seen	Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Keelsons	" " "	Sails	2 1/2 suits
Plank sheers	scraped	Clamps and Shelves	" " "	Anchors	No. of
Sheerstrakes	retanned & caulked	Ceiling	" " "	Cables	
Topsides		Rudder	" " "	Hawsers and Warps	
Wales		Copper	None When put on	Standing & Running Rigging	
Plank (Bottom) and Counter	Good				

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Good

The Rules, Section 54 having been complied with, we are of opinion that she is eligible to be Continued for 3 years from 1855. - B. W. Wymouth

The Amount of Fee.....£ 2 : - : - is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 2 : 6

Committee's Minute 24<sup>th</sup> December 1855

Character assigned Cont 1 for 3 Years



© 2019

Lloyd's Register Foundation