

S.S. for Asterisk

20141

REPORT of SURVEY for REPAIRS.

No. 138 Survey held at London Date 29th & 31st Jan^y 1856

on the Bark "Pearl" Master Davis

Tonnage 361 Built at Sunderland When built 1842
481

By whom built _____ Owners Collinson

Port belonging to London Destined Voyage Montreal

If Surveyed Afloat or in Dry Dock Comercial dock & on Donson's ways

Last Survey, No. 19603 Port London Classed 10 15 35 now B.A.
Cont. 52 - 3 35

REPAIRS Now done, in accordance with Rule Sec. 60. vessel laid on blocks, outside planking scraped bright from light watermark upwards, including plank sheers and waterways; the upper deck and comings, the upper and lower deck bolts and the planks through which they pass, the plank sheers, waterways, & beams; the hawse-timbers, knightheads, breast-hooks, transoms, floors, keelson, keel, rudder and treenails, have been examined and found to be in good condition.

Ship caulked from light watermark to Waterway seam.

R. A. J.
J. W. W.

Present Condition of the

Decks <u>good</u>	Treenails <u>good</u>	Windlass and Capstan <u>much, good</u>
Waterways <u>u</u>	Breasthooks and Stemson <u>u</u>	Pumps <u>2 of iron & bilge pumps</u>
Comings <u>u</u>	Transoms, Pointers, and Crutches <u>u</u>	Boats <u>3 in 11th good</u>
Upper Deck Beams & Fastenings <u>u</u>	Timbers of the Frame <u>u where seen</u>	Masts, Yards, &c. <u>u</u>
Lower Deck Beams & Fastenings <u>u</u>	Keelsons <u>u</u>	Sails <u>u</u>
Plank sheers <u>u</u>	Clamps and Shelves <u>u</u>	Anchors No. of <u>3 B, 1 S, 2 K</u>
Sheerstrakes <u>u</u>	Ceiling <u>u</u>	Cables <u>320 x 1 7/8</u>
Topsides <u>u</u>	Rudder <u>u</u>	Hawsers and Warps <u>11 x 9 x 7</u>
Wales <u>u</u>	Copper <u>YM L.M</u> When put on <u>1853</u>	Standing & Running Rigging <u>good</u>
Plank (Bottom) and Counter <u>u</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

This vessel is in a good and efficient state of repair, fit for the safe conveyance of dry and perishable cargoes to and from all parts of the world, and is, in our opinion, eligible to be classed F.S. 1 and to be marked in the Register book, S.S. 56.

The Amount of Fee.....£ : : is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 5 : -

Committee's Minute 5th February 1856

Character assigned F. Asterisk



© 2019

Lloyd's Register
Foundation

LON636-0436