

# REPORT of SURVEY for REPAIRS.

20177

No. 10 Survey held at London Date Jan<sup>ry</sup> 2<sup>nd</sup> 23<sup>rd</sup> 1856  
on the Barke "Rodiac" Master E. Jarvis  
Tonnage 320 Built at Salcombe When built 1852  
By whom built 340 Owners Balkwill & Co.  
Port belonging to Salcombe Destined Voyage   
If Surveyed Afloat or in Dry Dock Mountain Slip and dry docks

Last Survey, No. 1315 Port Dartmouth Classed 12 A 1

## REPAIRS

Now done, 12 planks in the wales found to be wormed on each side of the vessel have been renewed of Teak, (the fore hoods of English Oak) all the iron bolts in lodging knees, and throat bolts of hanging knees to lower deck beams have been renewed of metal. Vessel hung in shores, caulked from keel to upper part of wales, and re-sheathed with yellow-metal on paper.

The Owner requests the repairs may not be entered in the Books

## Present Condition of the

Decks <u>good</u>	Treenails <u></u>	Windlass and Capstan <u>good</u>
Waterways <u>good</u>	Breasthooks and Stemson <u></u>	Pumps <u>good</u>
Comings <u>good</u>	Transoms, Pointers, and Crutches <u></u>	Boats <u>3 good</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>good</u>	Masts, Yards, &c. <u>good and efficient</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>where seen</u>	Sails <u>good and efficient</u>
Planksheers <u>good</u>	Clamps and Shelves <u>seen</u>	Anchors No. of <u>3 B. 1 S. 1 No.</u>
Sheerstrakes <u>good</u>	Ceiling <u></u>	Cables <u>good and efficient</u>
Topsides <u>good</u>	Rudder <u></u>	Hawsers and Warps <u>good</u>
Wales <u>caulked</u>	Copper <u>Y. M. on paper</u>	Standing & Running Rigging <u>good</u>
Plank (Bottom) and Counter <u>caulked</u>	When put on <u>now done</u>	

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where seen

This vessel is now in good, and efficient condition and in my opinion eligible to remain as Classed 12 A 1

The Amount of Fee.....£ 1 : — : — is received by me,

Special..... 2 : 2 : —

Certificate (if required) — : — : —

Committee's Minute 25<sup>th</sup> February 1856

Character assigned 12 A 1



© 2019

Lloyd's Register  
Foundation

Lon636-0472