

# REPORT of SURVEY for REPAIRS.

20292

No. 410 Survey held at London Date April 19<sup>th</sup> 1856  
 on the Ship "Rummy mede" Master W Bueroos  
 Tonnage 720 Built at Sunderland When built 1854  
 By whom built \_\_\_\_\_ Owners Brass & Co  
 Port belonging to London Destined Voyage Australian  
 If Surveyed Afloat or in Dry Dock Union dry dock

Last Survey, No. 5403 Port Sunderland Classed 11 A 1

## REPAIRS

Now done; G. Metal sheathing stripped off and the vessel caulked from the keel to the fifth seam inside the waterway. Main deck waterway rebolted with an extra through bolt or dump of Yellow Metal in every beam and the Upper deck clamps rebolted with galvanized iron dumps - Resheathed with G. M on Paper -

Added to Hold beams 1 pair of vertical and 4 pairs of diagonal Knee Riders extending to take 2 bolts in the floors also 1 pair of vertical knees bolted with G. Metal -

## Present Condition of the

|                               |      |   |      |                            |               |
|-------------------------------|------|---|------|----------------------------|---------------|
| Decks                         |      | Treenails   |      | Windlass and Capstan       |               |
| Waterways                     |      | Breasthooks and Stemson                           |      | Pumps                      |               |
| Comings                       |      | Transoms, Pointers, and Crutches                  |      | Boats                      |               |
| Upper Deck Beams & Fastenings |      | Timbers of the Frame                              |      | Masts, Yards, &c.          | In good order |
| Lower Deck Beams & Fastenings | Good | Keelsons  | Good | Sails                      | and           |
| Planksheers                   |      | Clamps and Shelves                                |      | Anchors No. of             | sufficient    |
| Sheerstrakes                  |      | Ceiling   |      | Cables                     |               |
| Topsides                      |      | Rudder  |      | Hawsers and Warps          |               |
| Wales                         |      | Copper <u>1 M on paper</u> When put on <u>now</u> |      | Standing & Running Rigging |               |
| Plank (Bottom) and Counter    |      |   |      |                            |               |

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. new & good

This vessel is now in a good and efficient state and is eligible in my opinion to remain classed 11 A 1

The Amount of Fee.....£ : : is received by me, Thos W Wain

Special..... 2 : 2 : - } 11 A 1

Certificate (if required) : 5 : -

Committee's Minute 2<sup>nd</sup> May 1856

Character assigned 11 A 1

Charge Special £ 2.2.0 - received

Brass & Stanes 4, Cullum Street



© 2019

Lloyd's Register Foundation

LDN 637-0011