

# REPORT of SURVEY for REPAIRS.

20354

No. 128 Survey held at London Date 3<sup>rd</sup> to 21<sup>st</sup> April 1856  
 on the Ship "Bellisley" Master Parish  
 Tonnage 1014 Built at London When built 1844  
 By whom built 1102 Owners R. Green  
 Port belonging to London Destined Voyage Calcutta  
 If Surveyed Afloat or in Dry Dock Messrs Green's Dry Dock & Afloat in the East. I. Docks

Last Survey, No. 18965 Port London Classed 12 A1.

REPAIRS Now done in accordance with the Rules Sec<sup>54</sup> the vessel placed in Dry Dock, and scraped bright from the light water mark upwards, including the Planksheers, and Waterways Bolts and treenail driven out for Survey:— Repairs now done viz:— One new Topsail Sheet Bitt on the Port Side Waterways Comings, Wales, and upper courses of Topsides Caulked. Yellow Metal sheathing renewed on paper, from the light water mark upwards, Main Top and rigging to Main Mast all new, Fore and Mizzen Masts stripped and rigging refitted.—

The upper Deck and Comings, The upper and lower Deck Bolts, and the outside planks through which they pass, the Planksheer, waterways and beams, so far as they can be examined; the hawse timbers, Knight-heads, Breasthooks and transoms; the floors and keelsons, the keel and Rudder

Decks		Treenails	Windlass and Capstan
Waterways	} good	Breasthooks and Stemson	Pumps good
Comings		Transoms, Pointers, and Crutches	Boats 4 good
Upper Deck Beams & Fastenings		Timbers of the Frame	Masts, Yards, &c. good & sufficient
Lower Deck Beams & Fastenings	} when seen	Keelsons	Sails 2 good suits
Planksheers		Clamps and Shelves	Anchors No. of 3 B. 1 S. 2 1/2
Sheerstrakes		Ceiling	Cables good & sufficient
Topsides	} when seen	Rudder	Hawsers and Warps good
Wales		Copper	Standing & Running Rigging good
Plank (Bottom) and Counter		When put on	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good when seen

This vessel having undergone the whole of the requirements of the Rule Sec<sup>54</sup> and being in good and efficient condition, we are of opinion she is eligible to be continued for a period as described by the Rules A1 for

The Amount of Fee.....£ 5 : — : — is received by me, 4 years from 1856.

Special..... 3 : 3 : —

Certificate (if required) : 5 : —

Committee's Minute 6<sup>th</sup> June 1856

Character assigned Cont. for 4 years

H Boulds

W. W. W. W.

Lloyd's Register  
Foundation

100857-0064



20354 Jon

the planking outside, and trenails passing through from  
the light watermark upwards, the ceiling inside, and  
the frame and inner surface of the outside planking  
where it can be seen appear in good condition,  
and the ~~and~~ general form of the Ship unaltered.

H. Boulds



© 2019

Lloyd's Register  
Foundation