

20471

REPORT of SURVEY for REPAIRS.

Change of Owners & Re-entry of class

No. 339 Survey held at London Date June 10th to July 1st 1856
on the Brig "Alexander Wise" Master Jas. McKeen
Tonnage 278 Built at Sunderland When built 1839
By whom built _____ Owners J. Williams
Port belonging to London Destined Voyage Mediter
If Surveyed Afloat or in Dry Dock Gun Dry Dock
Springs 48

Last Survey, No. 825 Port Glasgow Classed 9th F. 1 Class over the
S.S. 52 3 53

REPAIRS

Now done, the Kulson and Nag Kulson renewed with Red Pine, bolted with Iron bolts; three planks on the starboard and three on the larboard side renewed with American Elm; one fore hood of the sheer strake on the larboard side and one plank of the Black strake renewed with Pitch pine; two lengths of Plank each side next the waterway and one shift abaft the Windlass renewed; one plank in the larboard upper course of bottom renewed with English Oak; the lower breast-board new with English Oak; a stern knee of English Oak added; a listing cut out of the Zinc sheathing all fore and aft at the Kul seam, ^{and at} wood ends forward and aft, and the Hams exposed Caulked. - Sixty fathoms of Chain renewed with ^{1 1/2} inch

Present Condition of the

Decks	Caulked	Treenails		Windlass and Capstan	
Waterways	Caulked	Breasthooks and Stemson		Pumps	
Gmings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame	Good where seen	Masts, Yards, &c.	Good and sufficient
Lower Deck Beams & Fastenings		Keelsons	New	Sails	
Plank sheers		Clamps and Shelves		Anchors No. of	
Seerstrakes	Caulked	Ceiling		Cables	
Topsides		Rudder		Hawsers and Warps	
Tales		Copper on Zinc	When put on 1834	Standing & Running Rigging	
Hulk (Bottom) and Counter					

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Good
She now appears in good Condition, fit for the safe conveyance of dry and perishable Cargoes to and from all parts of the world and eligible in my opinion to be re-entered in the Registry Book ¹ Asterisk B.

The Amount of Fee.....£ / : - : - is received by me,

Special..... / : / : -

Certificate (if required) : :

Committee's Minute 29th July 1856

Character assigned Ex. 1 asterisk



© 2019

Lloyd's Register Foundation

LOW634-0180