

20523

REPORT of SURVEY for REPAIRS.

and Restoration

No. Survey held at London Date 18th August 1856
 on the Ship "Owen Glendower" Master J. Watson Rev 11 Aug
1856
 Tonnage 911 Built at London When built 1839
 By whom built R. Green Owners R. Green
 Port belonging to London Destined Voyage Bombay
 If Surveyed Afloat or in Dry Dock Mrs Green's Lower Dock & Afloat

Last Survey, No. 19745 Port London Classed 12 M. S

REPAIRS

At the present time under "Special Survey" Rule Section 55.
 all the bolts in the range of each deck driven out and the planks taken out; the upper deck waterways, and plankshears and spirketting and the strake next the waterways on the lower deck in midships, taken out, the yellow metal sheathing from the upper course to keel stripped off a strake of bottom planks between the Wales and light masts taken out all fore and aft, a plank of ceiling at the floor heads on each side also taken out, the limbers cleared and the hooks forward exposed.

Now done; the Hawse timbers, knee of the head and fittings, 15 Soptimber on the Starboard and 18 on the Port side, 20 filling timbers on the starboard and 18 on the Port side, and all the Port-jills renewed with English Oak. 18 Cant timbers (forward) on the starboard, and 21 on the Port side also 12 Roughtree timbers on the starboard and 13 on the port side renewed with English and African Oak.

P.S.O.

Present Condition of the

Decks	good	Treenails		Windlass and Capstan
Waterways	new	Breasthooks and Stemson	Good	Pumps
Comings	good	Transoms, Pointers, and Crutches		Boats
Upper Deck Beams & Fastenings	new	Timbers of the Frame	do	Masts, Yards, &c.
Lower Deck Beams & Fastenings	new	Keelsons	do	Sails
Plankshears		Clamps and Shelves	do	Anchors No. of
Sheerstrakes	new	Ceiling	do	Cables
Topsides		Rudder	do	Hawsers and Warps
Wales	part new remaind good	Copper <u>S.M. on F.</u>	When put on <u>1856</u>	Standing & Running Rigging
Plank (Bottom) and Counter	good			

General Observations and Opinion.

Caulking of Bottom, Deck, & Waterways.

good -

This vessel has now been "Specially Surveyed" in accordance with Rules Section 55; the uppercourses of the bottom were examined by Mr Ritchie in June 1855; and at that time daubed with 6 strakes of Dantzig Fir on felt, fastened in accordance with the Rules. She is now in a good and efficient state of repair and is eligible in our opinion to be Restored. The Amount of Fee £ 5: : is received by me, £ 1 from 1855.

Restoration Special Rate... 10:10:0

Certificate (if required) : 5: -

F. W. Wawn.

Committee's Minute 19th August 1856Character assigned Restored to 1 for 8 Years from 1856

© 2019



Planking.

20523 Lon

The Strake in the upper course of bottom removed in accordance with the Rule, renewed with English and Dantze Oak. The binding strakes in the wales, with 2 after hoods on the Starboard and 3 on the Port side new of Greenheart, English and Dantze Oak. Blackstrakes and Spondes new of Pitch Pine except the fore hoods which are of English Oak, Sheerstrakes of Greenheart, Dantze and English Oak, Forecastle drifts of Dantze Oak.

The planksheers, spartekettins and midship waterway of the main deck and the Sheerstrakes, planksheers and Waterways of Poop renewed with Pitch Pine - Main deck waterway forward new of English Oak and strake next the same of Dantze Pin - The plank inside at the floor heads new of Dantze and African Oak - Lower deck fastenings of Galvanized and upper deck of common Iron. Entirely recaulked except 6 strakes of doubling on the upper course of bottom and the sheathing from thence downwards renewed upon Felt -

S.W.W.



© 2019

Lloyd's Register
Foundation