

# REPORT of SURVEY for REPAIRS.

No. 55 Survey held at London Date July 17. to Sep 15 1856  
 on the Ship "Julia" Master A. Baker  
 Tonnage 1035 Built at Quebec When built 1832  
 By whom built \_\_\_\_\_ Owners C. Gamm

Port belonging to London Destined Voyage \_\_\_\_\_

If Surveyed Afloat or in Dry Dock Mr Youngs Dry Dock & Victoria Dock

Last Survey, No. 18247 Port London Classed C.A. 1.

REPAIRS Now done, three shifts of deck each side which had been cut for Air Tubes renewed; Centre timbers introduced to the Bow ports; One upper deck beam which is badly shaken on the Starboard arm cross bolted with ten 1 1/2 Iron bolts, set up with nuts on plates and the shakes furred up; the Yellow Metal sheathing stripped off, the Ship hung in threes Caulked from the keel to the Metal line, all the butts from thence to the gunwale, the Manches, waterway seam, and new deck, her bottom resheathed with Yellow Metal on Felt.

When this Ship was placed in Dry Dock we found a quantity of putrid bilge water lying on the Ceiling in P. I. O.

Decks <u>Good</u>	Treenails _____	Windlass and Capstan _____
Waterways <u>Caulked</u>	Breasthooks and Stemson _____	Pumps _____
Comings <u>Good</u>	Transoms, Pointers, and Crutches _____	Boats _____
Upper Deck Beams & Fastenings <u>Good</u>	Timbers of the Frame _____	Masts, Yards, &c. _____
Lower Deck Beams & Fastenings <u>Good</u>	Keelsons <u>Good when</u>	Sails <u>Good &amp;</u>
Planksheers _____	Clamps and Shelves <u>Seen</u>	Anchors No. of <u>Eight</u>
Sheerstrakes <u>Butts Caulked</u>	Ceiling _____	Cables _____
Topsides _____	Rudder <u>Yellow Metal</u>	Hawsers and Warps _____
Wales _____	Copper <u>on Felt</u> When put on <u>Now</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter <u>Caulked</u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good  
 Apart from the defective arrangement for carrying off the bilge water, we are of opinion that she is in good and efficient condition, and fit to remain as classed C.A. 1.

B. Weymouth

The Amount of Fee.....£ 1 : 1 : is received by me,

Special..... : :

Certificate (if required) : :

Committee's Minute 16th September 1856

Character assigned C.A. 1



20570 Lon

the flat of the Hold, we feared that she had no  
water Courses, but on cutting a hole between ~~the~~ a  
floor and futtock found a water course, but the  
timbers are so close that there is not sufficient access  
for the water to pass to it.

B. Weymouth



© 2019

Lloyd's Register  
Foundation