

REPORT of SURVEY for ~~REPAIRS~~.

and Continuation

No. 58 on the Y³ Indian Chief Survey held at London Date July 28th 1856

Tonnage 410 Built at Sundelland Master Sinclair When built 1846

By whom built _____ Owners Wemyss' Park Brothers

Port belonging to Trasburgh Destined Voyage Algoa Bay

If Surveyed Afloat or in Dry Dock Bilbe's patent slip and afloat

Last Survey, No. 1883b Port London Classed 10 A 1

REPAIRS at the present time under "Special Survey" Rule Section 54. the whole of the outside planking from the light mark to the waterway seam, scraped bright; the yellow metal sheathing entirely stripped off, and bolts and trenails where required driven out for inspection -

Now done; the foremast piece of Keelson and Stenson knee renewed with English Oak, 4 Hold beams and one arm with Matrogany; Midship sheerstrakes on both sides of Matrogany, also 3 shifts of Wals on each side of the same - 3 after hoods on the port quarter and 1 in the bottom also 2 on the starboard side and the midship shift of Blackstrake renewed with English Oak - Quarter deck drifts renewed with Dantzic Fir - Trenails renewed from the plank sheers to the light mark, knee bolts to hold beams (removed) renewed with Copper - Recaulked throughout and resheathed with Yellow Metal upon felt -

Decks	Trenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Keelsons	Sails
Plank sheers	Clamps and Shelves	Anchors No. of
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <u>SM on F</u> When put on <u>now</u>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion. Caulking of Bottom, Deck, & Waterways. new and good
 This vessel has now been "specially surveyed" in strict accordance with the Rules Sec. 54. she is now in a good and efficient state and is eligible in our opinion to be Continued 3 A 1 from 1856

The Amount of Fee.....£ 5 : : : is received by me,
 Special..... 3 : 3 : : A. N. C.
 Certificate (if required) : :

Committee's Minute 14th October 1856
 Character assigned Cont 1 for 3 years