

21185

REPORT of SURVEY for REPAIRS.

and entry

No. 349 on the Barth Charles Brooke Master Baillie
Survey held at London Date 3rd Sept to 10th Nov 1856
Tonnage 296 Built at Shepston When built 1825
By whom built _____ Owners Scrutton & Co
Port belonging to London Destined Voyage London

If Surveyed Afloat or in Dry Dock on hard at steps Youngs dry dock and West India Dock
pt E & d 43

Last Survey, No. 19374 Port London Classed Muttel
ND 43 W. & d 43 N T Sls 54 Sips 54 Rest 40 - 7 1/2 C 10 1/2 E 34 S.S. 54

REPAIRS

Now done The metal sheathing on the bottom patched and dressed. Renewed the fore deck beam of Main Hatchway also the after hold beam of do with Greenheart & two & oak lodging knees to deck beam. added one pair of vertical iron hanging knees to hold beam at mainmast - through bolted with 1 1/2 in 4 metal. also renewed three shifts of ceiling plank on the Port side and two shifts of do on the Starboard side through bolted with 5/8 in 4 metal. the Ceiling caulked from the top of bilge to the keelson. also the deck partly.

Present Condition of the

Decks <u>plth Caulked</u>	Treenails	Windlass and Capstan <u>Efficient</u>
Waterways	Breasthooks and Stemson	Pumps <u>New Iron</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>3 in W</u>
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>good and</u>
Lower Deck Beams & Fastenings	Keelsons	Sails <u>2 cuts</u> and <u>different</u>
Planksheers	Clamps and Shelves	Anchors No. of <u>good and different</u>
Sheerstrakes	Ceiling	Cables <u>and</u>
Topsides	Rudder	Hawsers and Warps <u>and</u>
Wales	<u>1 Metal on</u> When put on <u>1857</u>	Standing & Running Rigging <u>Refitted</u>
Plank (Bottom) and Counter		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

This vessel is now in good condition, fit for the safe conveyance of dry and perishable cargoes to and from all parts of the world and in our opinion eligible to be re-entered EX 1 in the Register Book

The Amount of Fee.....£ / : - : - is received by me,

Special..... / : / : -

Certificate (if required) : :

Committee's Minute 11th November 1856

Character assigned EX 1 asterisk

Charge £1.1



© 2019
Lloyd's Register
Foundation
LON 637-0374