

REPORT of SURVEY for REPAIRS.

20761

No. 378 Survey held at London Date Nov 17 to 20 1856
 on the Ship "Charlotte Jane" Master Russell
 Tonnage 619 Built at Bristol When built 1840
 By whom built Patterson Owners Thomson & Co
 Port belonging to London Destined Voyage China
 If Surveyed Afloat or in Dry Dock In Messrs Billies & Co Dry Dock

Last Survey, No. 20551 Port London Classed 13 A 1

REPAIRS now done She having become very leaky during heavy weather on her passage from London to China which obliged her to put back and discharge Cargo. More of particulars in Special Report.

Yellow Metal Sheathing stripped off and renewed upon Sides, Ship hung in Shores, Bottom Caulked, a pair of Side Keelsons introduced abreast of Main Mast each 29 feet long, 16 x 16 of Iron Bars, through Bolted, at every floor, and First Buttress, these Keelsons raised for a length of ten feet to the height of Middle-line Riving Keelson, a Step athwartship fitted for the heel of Main Mast to bear equally upon the three Keelsons, about 30 feet of Salter's Keel replaced in way of the above, and four Slack Keelson Bolts replaced with larger size, four Yellow Metal Bolts in Hold Riders and two in Knees between Decks replaced

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } <u>Good</u>	Breasthooks and Stemson	Pumps
Comings } <u>Good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>In good order and</u>
Lower Deck Beams & Fastenings <u>all whole & sound</u>	Keelsons <u>d's</u>	Sails <u>Sufficient</u>
Planksheers	Clamps and Shelves <u>d's</u>	Anchors No. of <u>3 15K1</u>
Sheerstrakes <u>d's</u>	Ceiling <u>d's</u>	Cables
Topsides <u>d's</u>	Rudder <u>d's</u>	Hawsers and Warps
Wales <u>d's</u>	<u>Copper Metal on</u> When put on <u>now new</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>d's</u>	<u>Felt</u>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.	

This Ship now appears to be in good condition, eligible to remain Classed A 1

The Amount of Fee.....£ 2 : - : is received by me, J. Martin
 Special on Damage 5 : 5 :
 Certificate (if required) : 5 :

Committee's Minute 19th December 1856

Character assigned 13 A 1

For Special Survey and Report £5.5.0

record repair

L. J.



Lloyd's Register Foundation

LN 634-0446