

REPORT of SURVEY for REPAIRS.

21017

No. 87 Survey held at London Date Apr 23, 1857
 on the Bark "Viceroy" Master J. Brown
 Tonnage 667 Built at North Scotia When built 1849
 By whom built _____ Owners S. C. Stanger
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Commercial Dock and Messrs Fletcher's Dry Dock

Last Survey, No. 20171 Port London Classed A.1. S.S. 33-4 Tons

REPAIRS Now done in accordance with the Rules Sect 13
The vessel opened all fore and aft at the bilges
inside where the frame appeared in very fair
condition, bolts and treenails also driven and for
survey and found good. - Now done. - The fore
piece of Dog-Belson renewed of Baltic fir. The
yellow-metal stripped off the bottom, the vessel
caulked from keel to second seam of deck except
in way of wood sheathing ^{on upper course of bottom} ~~over walls~~ which was &
renewed in June 1853, a pair of metal dovetail plates
renewed at the fore end of keel, and several bolts of
braces renewed of metal, 5 short pieces of deck renewed,
and the yellow-metal renewed as felt.

Present Condition of the

Decks <u>good</u>	Treenails _____	Windlass and Capstan <u>good</u>
Waterways <u>" caulked</u>	Breasthooks and Stemson _____	Pumps <u>"</u>
Comings <u>good</u>	Transoms, Pointers, and Crutches _____	Boats <u>3 good</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>good</u>	Masts, Yards, &c. <u>good & app 3</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>where seen</u>	Sails <u>"</u>
Planksheers <u>good</u>	Clamps and Shelves <u>seen</u>	Anchors No. of <u>3 B. 13. 110</u>
Sheerstrakes <u>caulked</u>	Ceiling _____	Cables <u>"</u>
Topsides <u>"</u>	Rudder _____	Hawsers and Warps <u>good</u>
Wales <u>"</u>	Copper <u>off keel</u> When put on <u>now done</u>	Standing & Running Rigging <u>good</u>
Plank (Bottom) and Counter <u>"</u>	Caulking of Bottom, Deck, & Waterways <u>good where seen</u>	

General Observations and Opinion,

This vessel is now in good condition and in
our opinion fit to carry any cargoes and
eligible to remain as classed A.1. and
marked S.S. 33-4 yrs

The Amount of Fee.....£ _____ is received by me,

Special..... 1 : 1 : -

Certificate (if required) _____

Committee's Minute 24th April 1857

Character assigned A.1. S.S. 33-4 yrs

Charge for attendance £1.1

J. T. Light
Surveyor

Lloyd's Register
 Foundation

LON 638-0216