

REPORT of SURVEY for REPAIRS.

2111/5

No. 429 Survey held at London Date 24th Mar till 25 May 1857
 on the Ship Royal George Master
 Tonnage 486 Built at Hull When built 1820
 By whom built Owners G Marshall
 Port belonging to London Destined Voyage
 If Surveyed Afloat or in Dry Dock in the West India Dock

Last Survey, No. 19695 Port London Classed Rest 38-6 1/2 C 2 *B 1 S.S. 53

REPAIRS at present the flat of the lower deck removed
amidships and 13 new hold beams of iron bark
wood or African oak with lodging knees of wood
and iron and the old iron hanging knees refastened
thru' new beams - The Ceiling in the hold has also
been renewed in various parts fastened with deep
bolls of iron but not thro' fastened. The Stern Post has
been renewed from the tight water mark up above the
upper deck beam - during this repair it was
found that the Apron was very defective in the tween
decks and written notice was given to the owner
to renew it and to thro' fasten the renewed Ceiling

Present Condition of the

Decks <u>Good</u>	Treenails <u></u>	Windlass and Capstan <u></u>
Waterways <u></u>	Breasthooks and Stemson <u></u>	Pumps <u></u>
Comings <u></u>	Transoms, Pointers, and Crutches <u></u>	Boats <u></u>
Upper Deck Beams & Fastenings <u></u>	Timbers of the Frame <u></u>	Masts, Yards, &c. <u></u>
Lower Deck Beams & Fastenings <u>much new</u>	Keelsons <u></u>	Sails <u></u>
Planksheers <u>firm</u>	Clamps and Shelves <u></u>	Anchors No. of <u></u>
Sheerstrakes <u></u>	Ceiling <u></u>	Cables <u></u>
Topsides <u></u>	Rudder <u>unshipped</u>	Hawsers and Warps <u></u>
Wales <u></u>	Copper <u>Ym</u> When put on <u>1855</u>	Standing & Running Rigging <u></u>
Plank (Bottom) and Counter <u></u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

but as the Owner has not yet attended to this notice
we beg to recommend that this Ship's Character
be suspended until properly repaired

The Amount of Fee.....£ : : is received by me,


Special..... : :

Certificate (if required) : :

S. H. Ritchie

Committee's Minute 21st May 1857

Character assigned Expunged Character



© 2019

Lloyd's Register Foundation

LON 638-0271