

REPORT of SURVEY for REPAIRS.

21211

No. 728 Survey held at London Date June 9th 185 7
 on the M^r Eskdale Master London C. Neward
 Tonnage 416 Built at Sunderland When built 1854
 By whom built _____ Owners E. Graham
 Port belonging to Newcastle Destined Voyage Madras
 If Surveyed Afloat or in Dry Dock New Crane dry dock

Last Survey, No. 5347 Port Sunderland Classed 10 A 1

REPAIRS

Now done: In consequence of Decay: Four floors, nine first
 futlookes, twenty-five head and heel chocks, & seven through
 cross chocks between the main and mizen masts renewed, twenty-
 five ceiling planks lifted to remove the above; Ten feet of Wood
 keelson forward, renewed, also four old beam pillars and the
 Carlines to main hatch. Twenty six bolts in knee riders
 renewed. Yellow metal sheathing entirely stripped off
 recaulked and resheathed with G. Iron on Paper

Present Condition of the

Decks	} Good	Treenails	} Good	Windlass and Capstan	}
Waterways		Breasthooks and Stemson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings	} do	Timbers of the Frame	} where seen	Masts, Yards, &c.	} In good order
Lower Deck Beams & Fastenings		Keelsons		Sails	
Plank sheers	} where seen	Clamps and Shelves	} do	Anchors No. of	} Sufficient
Sheerstrakes		Ceiling		Cables	
Topsides	do	Rudder	do	Hawsers and Warps	
Wales	do	Copper <u>To Mon paper</u> When put on <u>now</u>		Standing & Running Rigging	
Plank (Bottom) and Counter	do				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. new and good

This vessel appears to be now in a good and efficient
 state of repair and eligible in our opinion to remain
 classed. 10 A 1

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 : -

Certificate (if required) : :

Committee's Minute 4th August 1857

Character assigned 10 A 1

Thos. W. Mawn

H. J. Boulds.

Special £ 2.2.0



© 2019

Lloyd's Register
 at Surgeons
 4/8/57

LON 638-0400