

21235

# REPORT of SURVEY for REPAIRS.

No. 92 Survey held at London Date 29<sup>th</sup> July 1857  
on the Barque "Tarrock Hall" Master J. Mouch  
Tonnage 375 Built at Garmouth When built 1837  
By whom built 434 390 tons Owners Boadington  
Port belonging to London Destined Voyage St. Kitts  
If Surveyed Afloat or in Dry Dock Messrs Greens dry dock

Last Survey, No. 20508 Port London Classed 12 \*A.1  
S.S. 54 C4 56

## REPAIRS

How done. — The lower stake of blackshale renewed fore and aft on both sides except the after hoods, 3 shifts from forward of upper stake of wale on the star<sup>a</sup> side renewed all of Pitch Pine and Plan<sup>c</sup> Oak. The yellow metal shipped down to the lightwater mark the upper course of bottom dubbed bright. 5 forehoods of ceiling in hold renewed on the star<sup>a</sup> side of Plan<sup>c</sup> Oak, 4 pairs of Iron hanging knees added to lower deck beams and fastened with yellow metal bolts. Caulked from lightwater mark to Gunwale. The yellow metal sheathing from lightwater marks upwards renewed on Felt

## Present Condition of the

Decks	good	Treenails		Windlass and Capstan	good
Waterways	"	Breasthooks and Stemson	good	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	where	Boats	"
Upper Deck Beams & Fastenings	good	Timbers of the Frame	seen	Masts, Yards, &c.	good order
Lower Deck Beams & Fastenings	where seen	Keelsons	good	Sails	and sufficient
Planksheers	good	Clamps and Shelves	"	Anchors	No. of 3 B 15 2K
Sheerstrakes	"	Ceiling	"	Cables	sufficient good
Topsides	"	Rudder	"	Hawsers and Warps	"
Wales	"	Copper	When put on part new	Standing & Running Rigging	"
Plank (Bottom) and Counter	good where seen		part 1854		

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where seen

This vessel is now in good and efficient condition "fit for the safe conveyance of dry and perishable goods to and from all parts of the world" and eligible in our opinion to remain as Classed \*A.1

The Amount of Fee.....£ : : — is received by me, J. H. Siltman  
Special..... / : / : —  
Certificate (if required) : : —  
Thos. Wm. Wain

Committee's Minute 18<sup>th</sup> August 1857

Character assigned Alterik  
repaired  
Special £1.1