

REPORT of SURVEY for REPAIRS.

21349

No. 26 Survey held at London Date 13 July 1857
 on the Barge "Yamar" Master Ross
 Tonnage 448 Built at Newport When built 1846
 By whom built Owners J. Weller
 Port belonging to London Destined Voyage
 If Surveyed Afloat or in Dry Dock Bridge dry dock

Last Survey, No. 1159 Port Newport Classed 12 A.1.

REPAIRS now done, Yellow metal sheathing stripped, dubbed the upper courses of bottom, and drove out treenails to prevent doing so when specially surveyed for continuation. Renewed the treenails driven out for examination, the whole of the out and in fastening of Hold Beam Waterway also the lower throat Bolt of staple standard iron knees with Yellow Metal, caulked from keel to third seam of deck waterways included, the vessel having been hung in shores, decks partially caulked, resheathed with Yellow Metal on felt.

Present Condition of the

Decks <u>Good</u>	Treenails <u>Good</u>	Windlass and Capstan <u>Good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>"</u>	Pumps <u>2 Metal</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>"</u>	Boats <u>3 in number</u>
Upper Deck Beams & Fastenings <u>"</u>	Timbers of the Frame <u>"</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>"</u>	Sails <u>Sufficient</u>
Planksheers <u>"</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3 B 18 2 k</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>Sufficient</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>Yellow Metal</u> When put on <u>now</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>	<u>on felt.</u>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways. <u>now done</u>	

This vessel is now in good and efficient condition and in our opinion eligible to remain as classed A.1.

The Amount of Fee.....£ : : is received by me,

Special..... 1 : 1 :

Certificate (if required) : 5 :

's Minute 6th October 1857

ter assigned 12th

Charge L 1st

record YM



© 2019

Lloyd's Register
Foundation

7200-159204