

REPORT of SURVEY for REPAIRS.

No. 242
on the Ship Java
Tonnage 1175
Built at Calcutta
When built 1813
By whom built
Owners J Hall jr & Comp^y
Port belonging to London
Destined Voyage to Ballast & ~~Wharves~~ ^{to} ~~as a~~ ^{Coal} ~~Ships~~ ^{Ships}
If Surveyed Afloat or in Dry Dock In Mess^{rs} Somes Dry Dock
x Gibraltar

Last Survey, No. 142816 Port Shool Classed ~~Star~~ ~~AE~~ /

REPAIRS done at the present time of damages sustained by grounding
in the River Mersy, and on Peel Rock in Gibraltar Bay
on her passage from Liverpool to Gibraltar more of particulars
in Special Report.

Yellow Metal sheathing stripped off and renewed upon
 Telt. On the Port side in a space of about ninety feet in
 length, and ten feet in depth, at Bilge and Flat of Bottom
 the Doubling replaced with new three inches thick, of American
 Elm and Red Pine Lir, fastened with short and thin Bolts
 of Yellow Metal as required Ship hung in Shores, main Bottom
 Caulked in way of new Doubling, and the Doubling throughout the
 Bottom Caulked, Foremost and Aftermost pieces of Balke keel
 and the Gripe new, Dove tail plates at Heel of Stem and Stern Post new
 a new Piece of Rudder, one new Hanging Knee to a Beam of Lower Deck,
 in lieu of that broken asunder, and three other knees introduced to those Beams which
 were worked

Present Condition of the
 Decks

Treenails

Windlass and Capstan

Decks <i>Worked</i>	Treenails	Windlass and Capstan
Waterways } <i>Good when seen</i>	Breasthooks and Stemson } <i>Good when seen</i>	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <i>In good order</i>
Lower Deck Beams & Fastenings } <i>d^o</i>	Keelsons <i>d^o</i>	Sails <i>and sufficient</i>
Planksheers	Clamps and Shelves <i>d^o</i>	Anchors No. of
Sheerstrakes <i>d^o</i>	Ceiling <i>d^o</i>	Cables
Topsides <i>d^o</i>	Rudder <i>d^o</i>	Hawsers and Warps
Wales <i>d^o</i>	Copper <i>Put on Metal</i> When put on <i>new new</i>	Standing & Running Rigging
Plank (Bottom) and Counter <i>Double d^o</i>	<i>on felt over</i>	
General Observations and Opinion,	Caulking of Bottom, Deck, & Waterways.	