

REPORT of SURVEY for REPAIRS.

21530

No. 337 Survey held at London Date 2nd January 1858
 on the Barge "Cleopatra" Master J. Millard
 Tonnage 331 Built at Sunderland When built 1837
 By whom built 360 Owners Gollings &c
 Port belonging to London Destined Voyage Venezuela
 If Surveyed Afloat or in Dry Dock Smithkin dry dock

No. 21530

ast Survey, No. 20455 Port London Classed 11 *A.1 SS. 54

REPAIRS
 of Damage, how done; Planksheer, Spirketting and
 Roughree Rail of raised quarter deck on the port side
 renewed of Pitch Pine, six Roughree stantions in way
 of the same renewed of Eng^l Oak. one Roughree
 Stantion on the star^d side in way of main rigging renewed
 of Eng^l Oak. recaulked from metal line to three
 seams of deck next the Waterway, main yard renewed.
 In consequence of decay. on the port side the
 sheerstrake of raised quarter deck renewed of P. Pine
 one Roughree stantion in way of main rigging renewed
 of Eng^l Oak. Fore Mast renewed.

Present Condition of the

Decks <u>good</u>	Treenails <u>good</u>	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stenson <u>good</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>where</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>seen</u>	Masts, Yards, &c. <u>good order</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>good</u>	Sails <u>and efficient</u>
Planksheers <u>good</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3 B. 1 S. 2 K</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>sufficient good</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>metal</u> (When put on <u>1856</u>)	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>good where seen</u>		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where seen

This vessel is now in good and efficient condition
 fit for the safe conveyance of dry and perishable cargoes to
 and from all parts of the world; and eligible in our

The Amount of Fee.....£ 1 : : opinion to remain as Classed *A.1
 is received by me,

Special..... : : J. H. Siltman

Certificate (if required) : : Pro. Wm. Warr.

Committee's Minute 29th January 1858

Character assigned A.1 Satisfactory

record of repairs

J. H.



Lloyd's Register
 Foundation
 LON 639-0205