

21552

**REPORT of SURVEY for REPAIRS.**

No. 373 Survey held at London Date 15<sup>th</sup> Jan<sup>y</sup> 4 to 2<sup>nd</sup> Feb<sup>y</sup> 1858  
 on the Ship Great Britain Master W. Wilson  
 Tonnage 467 Built at Roole When built 1843  
 By whom built \_\_\_\_\_ Owners Alexander  
 Port belonging to London Destined Voyage San Francisco  
 If Surveyed Afloat or in Dry Dock Nelson Dry Dock

Last Survey, No. 13753 Port Lpool Classed 12 A1  
 REPAIRS now done Cont 55. 4. 56

A shelf fitted to upper deck beams extending from abaft the break of the Poop to before the break of the Forecastle of Teak fitted over the hanging knees. New second transom of English Oak seven shifts of Plank in the buttocks on the Port side and ten on the Starboard side also of English Oak. defect in Keelson in the wake of Fore Mast: trimmed off and made good by the wider Keelson of extra thickness of Teak. through bolted with yellow metal. Five new wrought-iron stentions on the Port side and two on the Starboard side

## Present Condition of the

Decks <u>Good</u>	Treenails <u>Good where seen</u>	Windlass and Capstan <u>DN P.D. Good</u>
Waterways _____	Breasthooks and Stemson _____	Pumps <u>2</u>
Comings _____	Transoms, Pointers, and Crutches <u>p<sup>2</sup> new</u>	Boats <u>3</u>
Upper Deck Beams & Fastenings _____	Timbers of the Frame <u>Good where seen</u>	Masts, Yards, &c. <u>new fore mast &amp;c</u>
Lower Deck Beams & Fastenings _____	Keelsons _____	Sails <u>2 suits</u>
Planksheers _____	Clamps and Shelves _____	Anchors No. of <u>3 B. 1 S. 1 K</u>
Sheerstrakes _____	Ceiling _____	Cables <u>300 fms</u>
Topsides _____	Rudder _____	Hawsers and Warps <u>sufficient</u>
Wales _____	Copper <u>on Fell</u> When put on <u>now done</u>	Standing & Running Rigging _____
Plank (Bottom) and Counter <u>p<sup>2</sup> new</u>		

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good. now done

This vessel is in good and efficient condition. eligible in our opinion to remain as classed

A1

The Amount of Fee.....£ / : : is received by me,

Special..... : : }

Certificate (if required) : 5 : - }

Committee's Minute 5<sup>th</sup> February 1858

Character assigned Cont 47



© 2019

Lloyd's Register  
Foundation

LON639-0218



21552 Lon

The ship hung in shores and caulked from keel  
to waterway seam and the yellow metal sheathing  
renewed on Felt-

W. S. Humphreys



© 2019

Lloyd's Register  
Foundation