

21575

# REPORT of SURVEY for REPAIRS.

*and Change of Owners*

No. 626 on the Ship "Matoaka" Survey held at London Date 28<sup>th</sup> January 1858  
 Master Stevens  
 Tonnage 1323 Built at New Brunswick When built 1833  
 By whom built 1227 Owners Seymour & Co  
 Port belonging to London Destined Voyage Port Phillip  
 If Surveyed Afloat or in Dry Dock Sungley's dry dock

*Rep'd 8.2.58  
C.M.P.*

Last Survey, No. 14072 Port Spool Classed 7 A/

## REPAIRS

*Now done.* The throat bolts of iron hanging knees to upper deck Beams renewed, Sheathed from the upper edge of Wales sixteen shakes down with Am<sup>e</sup> Elm and 13<sup>e</sup> Fir 1 1/2 and 2 thick on felt fastened with Yellow Metal spikes, the planking under the same dubbed bright and examined bolts and treenails driven out for survey, and were found good, the ship recaulked throughout and resheathed with Yellow Metal on paper.

## Present Condition of the

Decks <u>good</u>	Treenails <u>good</u>	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stenson <u>good</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>where</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>seen</u>	Masts, Yards, &c. <u>good order</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>good</u>	Sails <u>and sufficient</u>
Plank sheers <u>good</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3B, 1S, 2K</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>sufficient good</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	Copper <u>Yellow Metal</u> When put on <u>now</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>good where seen</u>		

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. new and good where tried

*This vessel is now in good and efficient condition and eligible in our opinion to remain as Classed A/*

The Amount of Fee.....£ 3 : - : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 16<sup>th</sup> February 1858

Character assigned 77 record register  
Extra Attendance 2.2.0

*J. H. Tiltman*  
*Thos W. Hawn*