

# REPORT of SURVEY for REPAIRS.

21609

No. 104 Survey held at London Date 8<sup>th</sup> February 1858  
 on the Ship "Maori" Master Petherbridge  
 Tonnage 703 Built at Liverpool When built 1851  
 By whom built        Owners C. Lebbell  
 Port belonging to London Destined Voyage New Zealand  
 If Surveyed Afloat or in Dry Dock Limekiln dry dock

Last Survey, No. 21363 Port London Classed 13A1

## REPAIRS

Now done, in consequence of damage, the yellow metal sheathing stripped off and renewed upon felt, four planks of bottom on the port side forward renewed of Eng<sup>l</sup> Oak, Ship hung in shores and recaulked from keel to metal line, a false keel added of American Oak,  
 For decay, the stemson knee and mast step to Fore mast renewed of Eng<sup>l</sup> Oak,

## Present Condition of the

Decks <u>good</u>	Treenails <u>      </u>	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stemson <u>good</u>	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>where</u>	Boats <u>"</u>
Upper Deck Beams & Fastenings <u>good</u>	Timbers of the Frame <u>seen</u>	Masts, Yards, &c. <u>good order</u>
Lower Deck Beams & Fastenings <u>where seen</u>	Keelsons <u>good</u>	Sails <u>and sufficient</u>
Planksheers <u>good</u>	Clamps and Shelves <u>"</u>	Anchors No. of <u>3 B. 1 S. 2 K</u>
Sheerstrakes <u>"</u>	Ceiling <u>"</u>	Cables <u>sufficient good</u>
Topsides <u>"</u>	Rudder <u>"</u>	Hawsers and Warps <u>"</u>
Wales <u>"</u>	<u>On Metal</u> When put on <u>now</u>	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter <u>"</u>		

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tried

This vessel is now in good and efficient condition and eligible in our opinion to remain as Classed A1

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 : 2

Certificate (if required) : 5 : 5

Committee's Minute 12<sup>th</sup> March 1858

Character assigned 13A1

Extra Attendance       

£22.0



© 2019

Lloyd's Register Foundation

LON639-0270