

21155

# REPORT of SURVEY for REPAIRS.

No. 137 Survey held at London Date 26<sup>th</sup> March 1858  
 on the Barque "West" Master Ramsey  
 Tonnage 366 Built at Sunderland When built 1848  
 By whom built 409 Owners Thornton & Wests  
 Port belonging to London Destined Voyage Singapore  
 If Surveyed Afloat or in Dry Dock Union dry dock

Last Survey, No. 21044 Port London Classed 13 A1  
 57

## REPAIRS

Now done. - Yellow Metal sheathing stripped off and renewed upon Felt. the upper piece of Main and false Stem renewed with Eng<sup>l</sup> Oak. the upper piece of Apron with African Oak, the Knightheads and Hawse timbers renewed on both bows with Eng<sup>l</sup> Oak & Teak. the upper deck Hook and Luff piece renewed with Eng<sup>l</sup> Oak the forehoods of ceiling on both sides betwixt decks renewed with Mahogany and Eng<sup>l</sup> Oak. the Knee of Head refitted. Head Rails renewed, one iron hook added and one refitted and refastened. hawse pipes refitted. the bottom from keel to Metal line, and both bows recaulked.

## Present Condition of the

|   |  |                                     |
|---|--|-------------------------------------|
| Decks <u>good</u>                                 | Treenails <u>good</u>  | Windlass and Capstan <u>good</u>    |
| Waterways <u>"</u>                                | Breasthooks and Stemson <u>good</u>                            | Pumps <u>"</u>                      |
| Comings <u>"</u>                                  | Transoms, Pointers, and Crutches <u>where</u>                  | Boats <u>"</u>                      |
| Upper Deck Beams & Fastenings <u>good</u>         | Timbers of the Frame <u>seen</u>                               | Masts, Yards, &c. <u>good order</u> |
| Lower Deck Beams & Fastenings <u>where seen</u>   | Keelsons <u>good</u>   | Sails <u>and sufficient</u>         |
| Planksheers <u>good</u>                           | Clamps and Shelves <u>"</u>                                    | Anchors No. of <u>3 B. 1 S. 1 K</u> |
| Sheerstrakes <u>"</u>                             | Ceiling <u>"</u>   | Cables <u>sufficient good</u>       |
| Topsides <u>"</u>                                 | Rudder <u>"</u>  | Hawsers and Warps <u>"</u>          |
| Wales <u>"</u>                                    | When put on <u>Now</u>   | Standing & Running Rigging <u>"</u> |
| Plank (Bottom) and Counter <u>good where seen</u> | Caulking of Bottom, Deck, & Waterways. <u>good where tried</u> |                                     |

This vessel is now in good and efficient condition and eligible in our opinion to remain as Classed A1

The Amount of Fee.....£ 1 : — : — is received by me,

Special..... 2 : 2 : —

Certificate (if required) : : —

Committee's Minute 9<sup>th</sup> April 1858

Character assigned 13 A1

record keeper

J. H. Tiltman  
 Jos. W. Wawn



© 2019

Lloyd's Register  
 Foundation

LN639-0313