

*21740

REPORT of SURVEY for REPAIRS.

of Damage and Change of Owners

No. 267 Survey held at London Date 5th May 1858
on the Ship "Lillydale" Master Weatherall
Tonnage 606 Built at New Brunswick When built 1854
By whom built _____ Owners Anderson
Port belonging to St. John Destined Voyage Calcutta
If Surveyed Afloat or in Dry Dock Simsbury dry dock

Received by Mr. Weatherall

Last Survey, No. 20610 Port London Classed 7 A 1

REPAIRS

how done, - in consequence of damage, the wood sheathing on Wales, and Yellow Metal on the bottom stripped off. the Ship hung in shores and recaulked from the keel seam to seam of deck next the waterway, the wood sheathing on the Wales (nine strokes of 1 $\frac{1}{2}$ Lin on Felt fastened with Galvanized iron nails) and the Yellow Metal sheathing renewed upon Felt, the face piece to head knee and the cheeks on both sides renewed, a short fore hood on each side, and the house Pipes renewed, one iron knee Rider on the starboard side renewed, the main Mast, Fore Mast, and main topsail Yard renewed, Rigging refitted,

From other causes, the throat bolts of iron knees

Present Condition of the

Decks	<u>good</u>	Treenails		Windlass and Capstan	<u>good</u>
Waterways	"	Breasthooks and Stenson	<u>good</u>	Pumps	<u>two of iron new</u>
Comings	"	Transoms, Pointers, and Crutches	<u>where</u>	Boats	
Upper Deck Beams & Fastenings	"	Timbers of the Frame	<u>seen</u>	Masts, Yards, &c.	
Lower Deck Beams & Fastenings	"	Keelsons	<u>good</u>	Sails	
Planksheers	"	Clamps and Shelves	"	Anchors No. of	<u>Good</u>
Sheerstrakes	"	Ceiling	"	Cables	<u>and sufficient</u>
Topsides	"	Rudder	"	Hawsers and Warps	
Wales	"	<u>on Metal</u> When put on <u>new</u>		Standing & Running Rigging	
Plank (Bottom) and Counter	"	<u>on Felt</u>			

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. new and good

This vessel is now in good and efficient condition and eligible in our opinion to remain as Classed A1

The Amount of Fee.....£ 2 : : is received by me,

Special..... 2 : 2 :

Certificate (if required) : : -

Committee's Minute 11th May 1858

Character assigned 7 A 1

Special 2.2.0

record of damage repair

J. H. Pittman
Thos. W. Wain