

21833

## REPORT of SURVEY for REPAIRS.

for Continuation and Change of owners.

No. 534 on the Ship "Charles" Survey held at London Date June 14 to 24 1858  
 Master J. W. Callow  
 Tonnage 1047 Built at Quebec When built 1851  
 By whom built 1072 Owners Rogers, Gladstone & Co.  
 Port belonging to London Destined Voyage India  
 If Surveyed Afloat or in Dry Dock Globe Dry Dock Per Owners

Last Survey, No. 20297 Port London Classed 5 1 1. Lapsed.

REPAIRS now done in accordance with the Rules Sec<sup>ns</sup> 54, the vessel scraped bright from the light water-mark upwards, including the planks and waterways so as to expose the surface of the planks to view, bolts and treenails driven out for survey and found good. The vessel opened all fore and aft on each side by the removal of a strake of plank at the bilges on the inside in accordance with Sec<sup>n</sup> 63, and the frame found very sound.

Repairs now done. vessel caulked from keel to gunwale and the flat of upper deck. 24, put of false keel renewed forward, bolts and treenails were taken out for survey and now renewed, and the strakes at the bilges made good by shipping pieces between the riders, and 3 2 2 thick, a scrap piece fitted in sister ribs where found defective on each side, and the bottom sheathed with yellow-metal on felt. The Rudder head is very defective and could not be got out of the trunk for renewal while in

Present Condition of the Dry Dock, the Owners promised to make the same good

Decks	Chulked	Treenails	Windlass and Capstan	fit
Waterways	"	Breasthooks and Stemson	Pumps	"
Comings	good	Transoms, Pointers, and Crutches	Boats	good and sufficient
Upper Deck Beams & Fastenings	good	Timbers of the Frame	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	where seen	Keelsons	Sails	"
Planksheers	good	Clamps and Shelves	Anchors	No. of 3 B. 1 S. 1 H.
Sheerstrakes	caulked	Ceiling	Cables	good & sufficient - new 3 1/2 inch chain
Topsides	"	Rudder	Hawsers and Warps	good and one new 3
Wales	"	Copper	Standing & Running Rigging	good
Plank (Bottom) and Counter	"	When put on		
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways.		good where stated.

This vessel having undergone the whole of the requirements of the Rules Sec<sup>ns</sup> 63 & 54, and being in good condition, we are of opinion she is now eligible to be continued for the period allowed by the Rules viz: 3 years 1 1. from 1857, if the Rudder be made efficient during her time of loading.

The Amount of Fee.....£ 5 : - : - is received by me,

Special..... 5 : 5 : -

Certificate (if required) : 5 : -

Committee's Minute 29<sup>th</sup> June 1858

Character assigned Cont 1 for 2 Years from 1858

Charge £ 2 2 extra

S. L. 58 = 5 1/2

Lloyd's Register Foundation

CON640-0032

please see their letter attached,

The upper or main deck and cabins, the upper and lower  
holds, and the outside planks through which they pass, the  
plank-keels, waterways, and beams; the larboard timbers, ridge  
boards, lofts and transoms; the floors and partitions; the  
(under to be made good) planking outside, and the ironails put  
through from the light water mark upwards, the ceiling  
and the frame and inner surface of the outside planks  
where it could be examined appeared in good condition  
the sheer and general form of vessel unaltered.

J. T. n