

REPORT of SURVEY for REPAIRS.

No. 370 Survey held at London Date 16th June to 21st July 1858
 on the V. "Roxburgh Castle" Master M. H. Smith
 Tonnage 1049 Built at Switzerland When built 1852
 By whom built _____ Owners R. Green
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Up "Green's Lower dry Dock"

Last Survey, No. 2120 Port London Classed B. A. 1

REPAIRS *now done.*

Yellow Metal stripped off and the bottom cleaned down, four
upper Transoms of English Oak. 4 After cant Timbers on the Port side
and 2 short Counter Timbers of English Oak - in the fore body
4 lower Cant Timbers and one second Buttock on the Starboard side
and 4 lower Cant Timbers on the Port side of English Oak, a good
many Cheeks also of English Oak on both sides, and Stemson knee
of English Oak Yellow Metal bolted.

Outside planking: - 7 After hoods of buttock planking on the Starboard
side and 10 on the Port side of English Oak, one bow ship also
on each side of English Oak.

Inside planking: - 14 After ships of lower hold ceiling on the Port side
East India Stacks & 10 fore hoods on each side of English Oak and East
India Stacks

Both buttocks entirely repainted with English Oak. Iron pointers.
Aft wholly rebolted on the Port side and part bolted on the Starboard side
Transom knees partly rebolted, one crutch and one Breast hook refitted

Present Condition of the

Decks	<u>Good</u>	Treenails	<u>part new</u>	<u>Good</u>	Windlass and Capstan	
Waterways	<u>do</u>	Breasthooks and Stemson		<u>do</u>	Pumps	<u>In good</u>
Comings	<u>do</u>	Transoms, Pointers, and Crutches	<u>part</u>		Boats	
Upper Deck Beams & Fastenings	<u>do</u>	Timbers of the Frame	<u>new</u>		Masts, Yards, &c.	
Lower Deck Beams & Fastenings	<u>Firm</u>	Keelsons		<u>Good</u>	Sails	<u>order and</u>
Planksheers		Clamps and Shelves		<u>do</u>	Anchors No. of	
Sheerstrakes		Ceiling	<u>part new</u>	<u>do</u>	Cables	
Topsides	<u>Good</u>	Rudder		<u>do</u>	Hawsers and Warps	
Wales		<u>Yellow Metal on Paper</u>			Standing & Running Rigging	<u>Sufficient</u>
Plank (Bottom) and Counter	<u>part new</u>	<u>Copper</u>				
		When put on	<u>July/58</u>			

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Good where tried
This vessel is at present in good condition and
in our opinion eligible to continue as classed B. A. 1

The Amount of Fee.....£ 3 : - : - is received by me, 24/8/58

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 30th July 1858

Character assigned 13th August



© 2019

Deferred 30th July
 Repaired 13th
 to be applied for
 by order of the Committee
 in Classification

21888 Lon.
and bolts, recaulked from keel to gunwale, Waterways and the
seams of deck on each side next the Waterways, caulking after-
wards tried and found satisfactory - the bottom retailed on
paper - - New lower masts, cross jack yard and some small
spars -



© 2019

Lloyd's Register
Foundation