

REPORT of SURVEY for REPAIRS.

22014

No. 879 Survey held at London Date Sep^r 14 to 25th 1858
 on the Schooner Storia Master Juth Delain 2^d de Dain
 Tonnage 97 Built at Jersey When built 1850
 By whom built _____ Owners De Garis & Coth
 Port belonging to Jersey Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Gilbert's Ways

Last Survey, No. DD1 Port Jersey Classed S A 1.

REPAIRS now done in accordance with the Rules Sec^t 54, for Continuation, the vessel scraped bright from the light-water mark upwards, including the plank sheers and waterways, Bolts, and treenails driven and for survey.

Repairs done viz: - 3 short pieces of ceiling on each side in the run of vessel renewed of Cantzic fir. A great number of slack treenails in wales and topsides renewed, the whole of the yellow-metal stripped off the bottom, vessel caulked from keel to gunwale, and yellow-metal renewed on paper.

The upper or main deck and comings, the upper deck bolts and the outside planks through which they pass, the plank sheers, waterways and beams, so far as they could be examined; the knighthead, kause timbers, breast hooks &c. - so far as they could be seen, the keel, rudder, and other treenails, ceiling, and frame of vessel where seen appears in good condition, and the form of vessel unaltered.

Decks	<u>good</u>	Treenails	<u>good</u>	Windlass and Capstan	<u>good</u>
Waterways	<u>"</u>	Breasthooks and Stenson	<u>"</u>	Pumps	<u>"</u>
Comings	<u>"</u>	Transoms, Pointers, and Crutches	<u>"</u>	Boats	<u>good and sufficient</u>
Upper Deck Beams & Fastenings	<u>good</u>	Timbers of the Frame	<u>good</u>	Masts, Yards, &c.	<u>"</u>
Lower Deck Beams & Fastenings	<u>where seen</u>	Keelsons	<u>where</u>	Sails	<u>"</u>
Plank sheers	<u>good</u>	Clamps and Shelves	<u>seen</u>	Anchors	No. of <u>2 B. 13. 16.</u>
Sheerstrakes	<u>"</u>	Ceiling	<u>"</u>	Cables	<u>good and sufficient</u>
Topsides	<u>"</u>	Rudder	<u>"</u>	Hawsers and Warps	<u>"</u>
Wales	<u>"</u>	Copper	<u>of m. When put on now done on paper</u>	Standing & Running Rigging	<u>"</u>
Plank (Bottom) and Counter	<u>"</u>	Caulking of Bottom, Deck, & Waterways.	<u>good where tested.</u>		

This vessel having undergone the requirements of the Rules Sec^t 54, and being now in an efficient state of repair, we are of opinion she is eligible to be continued for a period as allowed by the Rules

The Amount of Fee.....£ 1 : - : is received by me,

Special..... 3 : 3 : -

Certificate (if required) : 2 : 6

Committee's Minute 8th October 1858

Character assigned 8 A 1

Contd. for 30 days

Lloyd's Register Foundation

LON640-0201