

REPORT of SURVEY for REPAIRS.

22025

No. 25 Survey held at London Date Aug 13th 1858
 on the Barge "Kaparima" Master R. Ewin
 Tonnage 358 Built at Bristol When built 1835
 By whom built 347 Owners Messrs Scrutton &
 Port belonging to London Destined Voyage Trinidad
 If Surveyed Afloat or in Dry Dock W. Smith's Dry Dock & W. J. Dock

Next Survey, No. 20230 Port London Classed 13 A. 1.

REPAIRS

Now done, the yellow metal sheathing renewed on Selt. the keel Caulked from keel to the fourth seam of deck inside the waterways. Tested the Caulking which proved satisfactory - A shelf piece of Green heart 11 sided by 8 moulded at the upper edge and four inches the lower. introduced, extending from the buff of the bows to about sixteen feet abaft the main mast, the hanging knees taken down, and fitted to the shelf piece. The shelf piece wrought on the Clamp -

Present Condition of the

Decks <u>part Caulked</u>	Treenails	Windlass and Capstan
Waterways <u>Caulked</u>	Breasthooks and Stemson	Pumps
Comings <u>Good</u>	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <u>Good where</u>	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings <u>firm</u>	Keelsons <u>seen</u>	Sails <u>suff</u>
Planksheers	Clamps and Shelves	Anchors No. of
Sheerstrakes <u>Caulked</u>	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	<u>Metal</u>	Standing & Running Rigging
Plank (Bottom) and Counter <u>Caulked</u>	<u>Copper on Felt</u> When put on <u>now</u>	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good -

She is now fit in my opinion to remain classed 13 A. 1.
B. Weymouth

The Amount of Fee.....£ : : is received by me,

Special..... / : / : -

Certificate (if required) : :

Committee's Minute 15th October 1858

Character assigned 13 A. 1 record
Change Special fee £ 1.1.0



© 2019
 Lloyd's Register
 Foundation
 LON640-0212