

# REPORT of SURVEY for REPAIRS.

22090

No. 64 Survey held at London Date Sep<sup>r</sup> 21<sup>st</sup> to Oct 27<sup>th</sup> 1858  
 on the S. "Saladin" Master J. Baillie  
 Tonnage 772 Built at Sunderland When built 1851  
 By whom built \_\_\_\_\_ Owners Henderson  
 Port belonging to London Destined Voyage \_\_\_\_\_  
 If Surveyed Afloat or in Dry Dock Princes dry dock

Last Survey, No. 21077 Port London Classed 13 A 1

## REPAIRS

Now done, all the breast hooks and fore hoods of ceiling on both sides removed from the after part of fore hatch forward, three shifts of ceiling on starboard and two on port side of fore-castle. Knight heads renewed with Teak, nineteen timbers and twelve chocks on the port and nineteen timbers and thirteen chocks on the starboard bow also one chock on floor renewed with English oak: Hooks all rebolted two lower deck skatings and four pieces of lower deck waterway new of English oak and Teak. Ceiling and shelves (removed) renewed with Teak & Eng: Oak; three fore hoods of topside on starboard and one on port bow renewed with Teak and Eng: Oak — Retreenailed with Eng: Oak from the sheerstrakes to turn of bilge. Rudder braces refastened where required, recaulked throughout and resheathed with yellow metal upon felt — Upper deck shelf through bolted with Yellow Metal —

## Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways		Breasthooks and Stems		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Keelsons		Sails	
Planksheers		Clamps and Shelves		Anchors No. of	
Sheerstrakes		Ceiling		Cables	
Topsides		Rudder		Hawsers and Warps	
Wales		Copper <u>Mon T</u> When put on <u>now</u>		Standing & Running Rigging	
Plank (Bottom) and Counter					

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tried

This vessel is now in good condition and is eligible in our opinion to remain classed 13 A 1

The Amount of Fee.....£ 2 : — : — is received by me,

Special..... 4 : 4 : —

Certificate (if required) : 5 : —

Committee's Minute 26<sup>th</sup> November 1858

Character assigned 13 A 1

Jos. McWain

A. Humphreys



© 2019

Lloyd's Register Foundation

LON 640-0270