

REPORT of SURVEY for REPAIRS.

Continuation

22129

Recd 15/12/58

No. 303
on the

Survey held at

London

Date Aug 12

Mo 23

1858

Ship Marlborough

Master

R. Kerr

Tonnage 1293

Built at

Newcastle

When built

1846

By whom built

Owners

Smith & Co

Port belonging to

London

Destined Voyage

If Surveyed Afloat or in Dry Dock

Messrs Wigram's Dry Dock & East India Dock

Last Survey, No.

21251

Port

London

Classed

12A. 1.

REPAIRS

Now done, the Yellow Metal sheathing stripped off the bottom, the keels' sides scraped bright from the light-water mark to the waterway seam, trenails and bolts driven out for sawing. The following renewed - viz - The fore mast and bowsprit, four planks of the floor head stuff with teak, middle piece to the bowsprit beam with teak, the bowsprit bitts and starboard cathead and one plank in the starboard upper course of bottom aft - The knee of Head additionally bolted, and a pair of iron cheeks introduced, the ship hung in shores and caulked from the keel to the second seam of deck inside the waterways, her bottom resheathed with Yellow Metal on felt. - The upper deck and Comings, the upper and lower deck bolts, and the

P. I. O

Present Condition of the

Decks	Good & Caulked	Treenails	Good where seen	Windlass and Capstan	Good and
Waterways	Caulked	Breasthooks and Stemson	Good	Pumps	Sufficient
Comings	Good	Transoms, Pointers, and Crutches	Good	Boats	
Upper Deck Beams & Fastenings	Good	Timbers of the Frame	Good where seen	Masts, Yards, &c.	New fore Mast & Bowsprit
Lower Deck Beams & Fastenings	where seen	Keelsons	" " "	Sails	Good & Sufficient
Planksheers	Scraped, Caulked	Clamps and Shelves	" " "	Anchors	No. of 3 B. S. 1/4
Sheerstrakes	and Painted	Ceiling	" " "	Cables	Good & Sufficient
Topsides		Budder	" " "	Hawsers and Warps	" " "
Wales		Yellow Metal	" " "	Standing & Running Rigging	Refitted & New
Plank (Bottom) and Counter	Caulked	Copper on felt	When put on now		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested

The Rules of Section 54 have been complied with - She is fit in our opinion to be continued A. 1. for 4 years from 1858.

The Amount of Fee.....£ 5 : - : - is received by me,

Special.....£ : : - 11/1/59

Certificate (if required) : : -

Committee's Minute 17th December 1858

Character assigned Cont A 1 for 4 years



© 2019

Lloyd's Register Foundation

LON640-0308

22129 Lon

Planks thro' which they pass, the plankers, waterways,
and beams, the haws & timbers, Knightheads, breasthooks and
transoms, the floors and Kellsoms, the Keel and rudder,
the planking outside, and the trimails passing thro'
from the light water mark upwards, the Ceiling inside,
and the frame and inner surface of the outside planking
all appear in good Condition where seen. -

Her Sheer and form remain unaltered. -

P. W. Weymouth
J. P. " Lighter



© 2019

Lloyd's Register
Foundation