

22230

REPORT of SURVEY for REPAIRS.

No. 85 Survey held at London Date June 28th May to 1858
 on the S. Kinoston Master R Weeks
 Tonnage 84 3 Built at Sunderland When built 1853
 By whom built _____ Owners J Sidgett
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Timekiln dry dock

New July
C.W.

Last Survey, No. 19765 Port London Classed 10 A 1
 55

REPAIRS

Now done; 65 lower deck knee rider bolts (throat & others) renewed with yellow metal. one hundred and eighteen additional through bolts of the same driven between the light mark and the metal line, and one hundred and thirty two iron through bolts driven above the metal line between the fore & mizzen masts; the counter plank all refastened; poop and fore-castle ^{additionally} secured by the drift plank next under the main rail being worked forward and aft ^{of English oak} over three rough tree timbers, bolted vertically through rail, and in and out through timbers; the ceiling plank of poop in the way of same also worked similar, and secured over the rough trees - False keel worked forward, one bottom plank (wormed) renewed with Elm. Recaulked from keel to plank - sheers and restreathed with yellow metal on felt on upper course and paper below -

Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways		Breasthooks and Stemson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Keelsons		Sails	
Planksheers		Clamps and Shelves		Anchors No. of	
Sheerstrakes		Ceiling		Cables	
Topsides		Rudder		Hawsers and Warps	
Wales		Copper <u>Monbr</u> When put on <u>now</u>		Standing & Running Rigging	
Plank (Bottom) and Counter					

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where tried

This vessel is now in good condition and is eligible in my opinion to remain as classed 10 A 1

The Amount of Fee.....£ 2: : is received by me,

Special.....£ 2: 2: : 21/2/59

Certificate (if required) : : :

Committee's Minute 22nd February 1859Character assigned 10 A 1

Record Dept



© 2019

Lloyd's Register
Foundation

LON640-0406